



2 OVERALL CONTEXT ELEVATION AT UNIVERSITY AVENUE
1" = 20'-0"



2 OVERALL CONTEXT ELEVATION AT BYRON STREET
1" = 20'-0"



1 KEY PLAN - PROPOSED SITE
1/64" = 1'-0"

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PROPOSED STREET ELEVATIONS
NEIGHBORHOOD CONTEXT

SCALE
AS NOTED



SHEET NUMBER

A3.0

660 UNIVERSITY
PALO ALTO, CA 94301



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PROPOSED ELEVATIONS


SCALE
AS NOTED

PROJ. N
TRUE N
SHEET NUMBER


A3.1A



3 WEST ELEVATION (BYRON STREET)
3/32" = 1'-0"



2 MATERIAL SWATCHES
NO SCALE



1 KEY PLAN - PROPOSED SITE
3/128" = 1'-0"

660 UNIVERSITY
PALO ALTO, CA 94301



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PROPOSED ELEVATIONS


SCALE
AS NOTED

PROJ. N
TRUE N
SHEET NUMBER


A3.1B



3 EAST ELEVATION
3/32" = 1'-0"



2 MATERIAL SWATCHES
NO SCALE



1 KEY PLAN - PROPOSED SITE
3/128" = 1'-0"

660 UNIVERSITY
PALO ALTO, CA 94301



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PROPOSED ELEVATIONS


SCALE
AS NOTED

PROJ. N
TRUE N
SHEET NUMBER


A3.2A



3 SOUTH ELEVATION
3/32" = 1'-0"



2 MATERIAL SWATCHES
NO SCALE



1 KEY PLAN - PROPOSED SITE
3/128" = 1'-0"

660 UNIVERSITY
PALO ALTO, CA 94301



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PROPOSED ELEVATIONS

SCALE
AS NOTED




SHEET NUMBER


A3.2B






3 NORTH ELEVATION (UNIVERSITY AVE)
3/32" = 1'-0"



2 MATERIAL SWATCHES
NO SCALE



1 KEY PLAN - PROPOSED SITE
3/128" = 1'-0"



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.22		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2



PROJECT NUMBER
21003

SHEET TITLE
BUILDING SECTIONS

SCALE
3/32" = 1'-0"
0 10'-8" 21'-4"

SHEET NUMBER

A3.3



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
ENLARGED ELEVATION



A4.0A

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




ARCHITECTS
KORTH SUNSERI HAGEY


ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003


SHEET TITLE
ENLARGED ELEVATIONS




A4.1A




2 ELEVATION
1/4"=1'-0"



1 FIRST FLOOR PLAN
1/4"=1'-0"



1 FIRST FLOOR PLAN
1/4"=1'-0"



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3


PROJECT NUMBER
21003

SHEET TITLE
ENLARGED SECTION




SHEET NUMBER

A4.1B




UNIT TYPE A_STUDIO_ 387 SF
TERRACE _ 60 SF
STUDIO

14 UNIT TYPE A




UNIT TYPE A-1_ 380 SF
TERRACE _ 70 SF
1-BEDROOM

1 UNIT TYPE A-1




UNIT TYPE B_ 398 SF
TERRACE _ 63 SF
STUDIO

27 UNIT TYPE B




UNIT TYPE B-1_ 530 SF
TERRACE 1_ 63 SF
TERRACE 2_ 63 SF
1-BEDROOM W/ OFFICE

2 UNIT TYPE B-1




UNIT TYPE C_STUDIO_ 385 SF
TERRACE _ 60 SF
STUDIO

3 UNIT TYPE C




UNIT TYPE C-1_ 551 SF
TERRACE _ 115 SF
1-BEDROOM

2 UNIT TYPE C-1




UNIT TYPE D_ 551 SF
TERRACE _ 60 SF
1-BEDROOM

5 UNIT TYPE D




UNIT TYPE E_ 755 SF
TERRACE _ 63 SF
TERRACE 2_ 60 SF
2-BEDROOM

6 UNIT TYPE E




UNIT TYPE G_ 287 SF
TERRACE _ 60 SF
TERRACE 2_ 67 SF
STUDIO

1 UNIT TYPE G




UNIT TYPE F_ 394 SF
TERRACE _ 435 SF
STUDIO

1 UNIT TYPE F




UNIT TYPE F-1_ 426 SF
TERRACE _ 471 SF
STUDIO

1 UNIT TYPE F-1



UNIT TYPE F-2_ 452 SF
TERRACE _ 540 SF
1-BEDROOM

1 UNIT TYPE F-2



UNIT TYPE M_ 536 SF
1-BEDROOM

1 UNIT TYPE M

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003



SHEET TITLE
**PROPOSED TRASH ROOM &
UNIT PLANS**

SCALE
1/8" = 1'-0"



SHEET NUMBER

A5.1




ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
ENLARGED DETAILS

SCALE
AS NOTED



660 UNIVERSITY
PALO ALTO, CA 94301

 **THE
Guzzardo
Partnership, INC.**
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com


ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE

LANDSCAPE PLAN - GROUND FLOOR

SCALE



L 1.1

UNIVERSITY AVE


SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301


THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

BYRON STREET


MIDDLEFIELD ROAD



SECTION AA




SHORT-TERM BIKE RACK ENLARGEMENT



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE PLAN - GROUND FLOOR




L 1.1A

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

UNIVERSITY AVE




ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE PLAN - ROOF

SCALE




SHEET NUMBER

L 1.2

660 UNIVERSITY
PALO ALTO, CA 94301

THE
**Guzzardo
Partnership, INC.**
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

UNIVERSITY AVE



MIDDLEFIELD ROAD


BYRON STREET

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE PLAN - ROOF

SCALE



L 1.2A

Site



Pedestrian Unit Paver Pattern



Pedestrian Accent Paving Color



Open Wire Omega Fence near Public Rights of Way for Pedestrian and Vehicular Visibility-6' Height



Existing Concrete Foundation Wall (Along Property Line Near Large Coast Live Oak) to Remain



Horizontal Wood Slat Screen Fence - 7' Height



Wood Deck on Grade



Welle Circular Bike Rack-Silver



Bollard Light



Bollard Light



Precast Planter on Decorative Gravel over Existing Asphalt



Precast Planter on Decorative Gravel over Existing Asphalt



Raised Concrete Treatment Planter
Height above grade varies in different site conditions.
See plans

Roof Deck



Light and Raised Planter on Roof Deck



Light and Planter on Roof Deck



Low Bowl Planter on Roof Deck



Low Bowl Planter on Roof Deck



Unit Paving on Pedestals and Wood Deck

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE IMAGERY

SCALE

SHEET NUMBER

L 2.1

UNIVERSITY AVE

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

Plant callouts in pots are per pot, typ.

MIDDLEFIELD ROAD

BYRON STREET

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PLANTING PLAN - SITE



SCALE: 1" = 10'-0"
0' 5' 10' 20'

SHEET NUMBER

L 3.1

PLANT PALETTE

TREES- all 36" box							SUITABLE FOR STORMWATER TREATMENT
KEY	QTY	BOTANICAL NAME	COMMON NAME	COMMENTS/SPACING	WUCOLS	NOTES	
PLA ACE	3	Platanus acerifolia "Columbia"	Columbia London Plane Tree	Standard	Medium	Regionally Appropriate	
PRU ILI	4	Prunus ilicifolia ssp. lyonii	Catalina Cherry	Standard	Low	California Native	
SHRUBS, GROUNDCOVERS AND GRASSES --all 5 gallon size							SUITABLE FOR STORMWATER TREATMENT
KEY	QTY	BOTANICAL NAME	COMMON NAME	COMMENTS/SPACING	WUCOLS	CALIFORNIA NATIVE	
AGV	52	Anigozanthos 'Gold Velvet'	Gold Kangaroo Paw	24" o.c.	Low	Regionally Appropriate	
CAC	71	Carex californica	California Sedge	24" o.c.	Low	California Native	
CEO	7	Cephalanthus occidentalis	Buttonbush	48" o.c.	Medium	California Native	
CHO	24	Chondropetalum tectorum	Small Cape Rush	36" o.c.	Low	Regionally Appropriate	
FES	159	Festuca californica	California Fescue	24" o.c.	Low	California Native	
HET	14	Heteromeles arbutifolia	Toyon	48" o.c.	Low	California Native	
IRD	127	Iris douglasiana	Pacific Coast Iris	12" o.c.	Low	California Native	
JUP	99	Juncus patens	Blue Rush	24" o.c.	High	California Native	
MCA	35	Myrica californica	California Wax Myrtle	36" o.c.	Medium	California Native	
MUH	42	Muhlenbergia rigens	Deer Grass	24" o.c.	Low	California Native	
RSA	21	Ribes sanguineum	Red Flowering Currant	30" o.c.	Low	California Native	
SAL	36	Salvia clevelandii 'Winfred Gillman'	Cleveland Sage	24" o.c.	Low	California Native	
ACCENT SHRUBS, GRASSES AND PERENNIALS- all one gallon size							SUITABLE FOR STORMWATER TREATMENT
CK	28	Calamagrostis x a. 'Karl Foerster'	Feather Reed Grass	36" o.c.	Medium	CALIFORNIA NATIVE	
LL	36	Lomandra longifolia 'Lime Tuff'	Dwarf Mat Rush	24" o.c.	Low	Regionally Appropriate	
ST	24	Stipa arundinacea	New Zealand Wind Grass	18" o.c.	Low	Regionally Appropriate	
SB	67	Sisyrinchium bellum	Blue-eyed grass	24" o.c.	VeryLow	CALIFORNIA NATIVE	
SM	66	Senecio madraliscae	Blue Chalk Sticks	24" o.c.	VeryLow	CALIFORNIA NATIVE	
GROUNDCOVERS- all one gallon size							SUITABLE FOR STORMWATER TREATMENT
MH	84	Mahonia repens	Creeping Oregon Grape	24" o.c.	Low	California Native	

- Notes:
- Plants with low WUCOLS ratings are drought tolerant and regionally appropriate species. Plants noted are Native to California. Other plants, not in either of these two categories are well adapted to Palo Alto. Habitat forming column refers to food value of flowers or fruit for small animals, birds, butterflies and other insects in addition to shelter for some insects.
 - Do not use chemical fertilizers, pesticides, herbicides or commercial soil amendment. Use Organic Materials Review Institute (OMRI) materials and compost. Refer to the Bay-Friendly Landscape Guidelines: <http://www.stopwaste.org/resource/brochures/bay-friendly-landscape-guidelines-sustainable-practices-landscape-professional> for guidance
 - Avoid compacting soil in areas that will be unpaved. All planting areas to receive 3" layer of bark mulch.

The approximate total quantity of plants proposed is 1007. Of these plants, 932 are native which totals 92.6% Native plantings.

WATER EFFICIENT LANDSCAPE WORKSHEET

This worksheet is filled out by the project applicant and it is a required element of the Landscape Documentation Package.

Reference Evapotranspiration (ETo) 43.1							
Hydrozone # /Planting Description ^a	Plant Factor (PF)	Irrigation Method ^b	Irrigation Efficiency (IE) ^c	ETAF (PF/IE)	Landscape Area (sq. ft.)	ETAF x Area	Estimated Total Water Use (ETWU) ^d
Regular Landscape Areas							
Low Water-Use Plants	0.3	Drip	0.81	0.37	2,877	1,064	28,445
Moderate Water- Use Plants	0.5	Drip	0.81	0.62	273	169	4,523
					(A)	(B)	
				Totals	3,150	1,234	32,968
Special Landscape Areas							
					(C)	(D)	
				Totals	0	0	
						ETWU Total	32,968
							37,878

^aHydrozone #/Planting Description
E.g
1.) front lawn
2.) low water use plantings
3.) medium water use planting

^bIrrigation Method
overhead spray
or drip

^cIrrigation Efficiency
0.75 for spray head
0.81 for drip

^dETWU (Annual Gallons Required) = Eto x 0.62 x ETAF x Area
where 0.62 is a conversion factor that converts acre- inches per acre per year to gallons per square foot per year.

^eMAWA (Annual Gallons Allowed) = (Eto) (0.62) [(ETAF x LA) + ((1-ETAF) x SLA)]
where 0.62 is a conversion factor that converts acre-inches per acre per year to gallons per square foot per year, LA is the total landscape area in square feet, SLA is the total special landscape area in square feet, and ETAF is .55 for residential areas and 0.45 for non-residential areas.

ETAF Calculations
Average ETAF for Regular Landscape Areas must be 0.55 or below for residential areas, and 0.45 or below for non-residential areas.

Regular Landscape Areas	
Total ETAF x Area (B)	1,234
Total Area (A)	3,150
Average ETAF	0.40

All Landscape Areas	
Total ETAF x Area (B+D)	1,234
Total Area (A+C)	3,150
Sitewide ETAF (B+D) ÷ (A+C)	0.40



Festuca californica



Helictotrichon sempervirens



Heteromeles arbutifolia



Lomandra 'Lime Tuff'



Muhlenbergia rigens



Myrica californica



Rhamnus c. 'Mound San Bruno'



Salvia c. 'Winfred Gilman'



Stipa arundinacea



Sisyrinchium angustifolium



Calamagrostis acutiflora 'Stricta'



Anigozanthos 'Gold Velvet'



Sisyrinchium bellum



Mahonia repens

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
**Guzzardo
Partnership, INC.**
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PLANTING PALETTE & IMAGERY &
WELO CALCULATIONS

SCALE

SHEET NUMBER

L 3.2

660 UNIVERSITY
PALO ALTO, CA 94301




Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
PLANTING PLAN - ROOF DECK

SCALE




L 3.3

UNIVERSITY AVE

BYRON STREET

MIDDLEFIELD ROAD




TREE DISPOSITION LEGEND

Total Existing Trees on Site	24
Disposition	Regulated Trees
Tree to be Preserved	0
Tree to be Preserved Off-Site	6
Total Trees Preserved	6
Removed, Poor Condition	3
Removed, Project Re-Design	15
Total Trees Removed	18
Total Proposed Trees	7
Total Trees on Future Site	13

Note:
- See Arborist Report by Arbor Resources dated November 19, 2021 for specific information about existing trees.

Trees NO. Proposed for Removal	Tree Name	Trunk Diameter (in.)	Canopy Spread (ft.)	Numbers of Replacement Trees Needed (24" Box Size)	Numbers of Alternative Trees Needed (36" Box Size)	Numbers of Alternative Trees Needed (48" Box Size)
#4	Grove privet (Ligustrum laurum)	6	10	3	2	
#5	Grove privet (Ligustrum laurum)	13	20	3	2	
#6	Common plane tree (Platanus occidentalis)	10	35	4		2
#11	Olive tree (Olea europaea)	8,8	10	3	2	
#13	Raywood ash (Fraxinus s. 'Raywood')	12	15	3	2	
#14	Raywood ash (Fraxinus s. 'Raywood')	11	20	3	2	
#15	Raywood ash (Fraxinus s. 'Raywood')	6	15	3	2	
#16	Raywood ash (Fraxinus s. 'Raywood')	15	20	3	2	
#17	Purple Robin locust (Robinia 'Purple Robin')	6	20	3	2	
#18	Purple Robin locust (Robinia 'Purple Robin')	5	20	3	2	
#19	Crape myrtle (Lagerstroemia indica)	5	10	3	2	
#21	Crape myrtle (Lagerstroemia indica)	6	10	3	2	
#22	Crape myrtle (Lagerstroemia indica)	6	10	3	2	
#23	Crape myrtle (Lagerstroemia indica)	6	10	3	2	
#25	Yew pine (Podocarpus macrophylla)	8	10	3	2	
				Total Numbers of Replacement Trees Needed (24" Box Size)	46	
				Total Numbers of Alternative Trees Needed for Replacement (36" Box Size)	28	Total Proposed Tree (36" Box Tree)
				Total Numbers of Alternative Trees Needed for Replacement (48" Box Size)	2	Total Proposed Tree (48" Box Tree)
					5	Total Numbers of Alternative Trees Needed On Site (36" Box Size)
					0	Total Numbers of Alternative Trees Needed On Site (48" Box Size)
						23
						2



SMITH DEVELOPMENT


660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE




SHEET NUMBER

L 4.1

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.** For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.



TRIE DISCLOSURE STATEMENT
City of Palo Alto

CITY OF PALO ALTO
Planning Division, 250 Hamilton Avenue
Palo Alto, CA 94301
(850) 328-2441
<http://www.cityofpaloalto.org>

Palo Alto Municipal Code, Chapter 8.10.040, requires disclosure and protection of certain trees located on private and public property, and that they be shown on approved site plans. A completed disclosure statement is an important building permit application that includes exterior work, all demolition or grading permit applications, or other development activity.

PROPERTY ADDRESS:

Are there Regulated trees on or adjacent to the property? YES NO (If no, proceed to Section 4)

[Sections 1-4 MUST be completed by the applicant. Please circle and/or check where applicable.]

1. Where are the trees? Check those that apply. **(Plans must be submitted showing over 4" diameter trees)**

☐ On the property
☒ On adjacent property overlooking the project site
☒ In the City planter strip or right-of-way easement within 30' of property line (Street Trees)*

*Street trees require special protection by a fenced enclosure, per the attached instructions. Prior to receiving any permit, you must provide an authorized Street Tree Protection Verification form by calling Public Works Operations at 493-9937 for inspection of required type I, II or III fencing (see attached Detail 100).

2. Are there any Protected or Designated Trees? YES NO

☒ Protected Tree (s)
☐ Designated Tree (s)
☒ Overhanging the property

3. Are there activity or grading within the drip-line? (radius 10 times the trunk diameter) of these trees? YES NO

If 'Yes', a **Tree Preservation Report** must be prepared by an ISA certified arborist and submitted for review (see TTM, Section 6.25). Attach this report to Sheet 1-L, Tree Protection, its Part of the Plant, per Site Plan Requirements.

4. Are the Site Plan Requirements* completed? YES NO

****Protection of Regulated trees during development require the following: (1) Plans must show the measured trunk diameter and canopy spread; (2) Plans must demonstrate, as a bold shaded line, a fenced enclosure area up to the drip-line, per Sheet 1-T and M663 -**

<http://www.cityofpaloalto.org/TreeForms.html> (See also TTM, Section 2.15 for area to be fenced)

5. I, the undersigned, agree to the conditions of this disclosure: I understand that knowledge or negligence providing false or misleading information in response to this disclosure requirement constitutes a violation of the Palo Alto Municipal Code Section 8.10.040, which can lead to criminal penalties and legal action.

Signature: *Paul E. Lettieri* Print: Paul T. Lettieri Date: 05/13/2022

(Prop. Owner or Agent)

FOR STAFF USE.

Protective Fencing
Sections 5-6 must be completed by staff for the issuance of any development permit (demolition, grading or building permit).

5. Protected Trees The specified tree fencing is in place. A written statement is attached verifying that protective fencing is correctly in place around protected and/or designated trees. YES NO

(N/A if there are no street trees, check here C)

6. Street Trees A signed Public Works Street Tree Protection Verification form is attached. YES NO

(N/A if there are no street trees, check here C).

Regulated Trees - a) Street trees (see public property); b) Protected trees - Coast Live Oaks or Valley Oaks which are 13.5" in diameter or larger, Coast Redwoods which are 18" in diameter or larger, when measured 5' above natural grade; and Heritage trees trees designated by City Council; and c) Designated Trees - commercial or non-residential property trees, which are part of an approved landscape plan.

Palo Alto Tree Technical Manual (TTM) contains instructions for all requirements for this form, available at <http://www.cityofpaloalto.org/planning-community/tree-technical-manual>

S:\Plan\Public\Arbor\Tree Protection Info\Tree Disclosure Statement

Revised 08/06

For written specifications associated with illustrations below, see Public Works Specifications Section 31

Tree Protection Zone (TPZ) shown in gray (radius of TPZ equals 10 times the diameter of the tree 10 feet, whichever is greater).

• Restricted activity area – see Tree Technical Manual Sec. 2.14(5).

• Restricted treekeeping area – see Tree Technical Manual Sec. 2.20(C)-(D), any proposed removal or form work within TPZ of a protected tree requires approval from Public Works Operations. Call 650-446-9553.

For all Ordinance Protected and Designated Trees, the applicant is to develop a Tree Protection Plan (TPP) for the project. The applicant's project approval is contingent on the plans.

Type I Tree Protection

Note: Ordinance Protected & Designated Trees. Issuance of a permit requires applicant's project arborist written verification Type I (as-needed) concurrently according to the plans and Tree Preservation Report

Any instrument sidewalk or curb replacement or treekeeping requires approval.

Type II Tree Protection

Any proposed trench in TPZ requires approval from TPZ 2.20 (C) written installation.

Note: Street Trees. Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.

Type III Tree Protection

(to be used only in absence of Public Works Operations)

Tree fencing is required and shall be erected before bonding, grading or concrete begins.

Rev.	By	Date	Description
01	DBS	01/04/02	
01	DBS	06/04/04	
01	DBS	06/10/06	

Scale: NTS

City of Palo Alto Standard

Tree Protection During Construction

Approved by: Clave Dockter

Permit No. 2006

Dwg No. 605

APPENDIX J

**PALM ALTO
STREET TREE PROTECTION INSTRUCTIONS
—SECTION III—**

3-1. General

- A. Tree protection has three primary functions.** 1) to keep the foliage canopy and branching structure clear of adjacent buildings, structures, and activities; 2) to protect the trunk and crown of trees from construction-related and non-competed state and 3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted to the minimum.
- B. The Tree Protection Zone (TPZ) is a restricted area around the base of the tree with a radius of six-times the diameter of the tree's trunk at its base, whichever is greater, enclosed by fencing.**

3-2. Reference Documents

- A. Detail 065' – Illustration of situations described.**
- B. Tree Technical Manual (T2M) Form (<https://www.cityofpaloalto.org/treeview>)**
- C. Treeing Restriction Signs (T2M, Section 3.03)**
- D. Arborist Reporting Protocol (T2M, Section 3.03)**
- E. Site Plan Formwork (T2M, Section 3.03)**
- F. Tree Disclosure Statement (T2M, Appendix A)**

3-3. Street Tree Verification (STV) Form (<https://www.cityofpaloalto.org/treeview>)

3-4. Excavation

- A. Type I Tree Protection:** The fence shall enclose the entire TPZ of the tree(s) to be protected throughout the life of the construction project. The fence shall be installed on existing or new concrete curbs that will not be demolished, then the posts may be supported by an optional grade level concrete base, if approved by Public Works Operations.
- B. Type II Tree Protection:** For trees situated within a planting strip, *only*, the planting strip and yard side of the TPZ shall be enclosed with the required chain link fencing to prevent fencing in order to keep the sidewalk and trees open for public use.
- C. Type III Tree Protection:** To be used only with approval of Public Works Operations. Trees situated in the front boulevard or sidewalk strip or sidewalk strip and boulevard strip shall be enclosed with the required chain link fence and covered with 2-inch glued high chain wood slat boards secured by staples (that shall not be allowed to injure the bark). During installation of the plastic fencing, care must be taken to avoid damaging any other nearby branches. Many limbs may also require plastic fencing as directed by the City Arborist.
- D. Site, type and area to be fenced:** All trees to be protected shall be protected within a 40' foot high chain link fence. Fences are to be mounted on two-inch diamond galvanized iron posts, driven into the ground at least 4 feet deep to a maximum 18 inch spacing. Fencing shall be attached to the existing curb, unless specifically approved on the STV Form.
- E. "Warning" sign:** A warning sign shall be weather proof and prominently displayed on each side at 20-foot intervals. The sign shall be minimum 8.5 inches x 11 inches and must place in half inch letter "WARNING - Tree Protection Zone - This fence shall not be removed and is subject to a fine according to the City of Palo Alto Section 16.110".
- F. "Warning" Tree fencing shall be erected before demolishing, grading or construction begins and remain in place until final inspection of the project is complete. The removal of the TPZ, Work of the City, or soil disturbance in the TPZ requires approval by the project arborist or City Arborist in the case of work around Street Trees. Excavations within the public right of way require a Street Work Permit from Public Works.**

3-5. During construction

- A. All neighbors' trees not within the project site shall be protected from impact of any kind.**
- B. The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Sections 8.04.070 of the Palo Alto Municipal Code.**
- C. The following tree preservation measures apply to all trees to be retained:**
 - a. No storage of materials, fuels, or equipment shall be permitted within the TPZ.
 - b. The ground under and around the tree canopy area shall not be altered.
 - c. Trees to be retained shall be irrigated, treated and maintained as necessary to ensure survival.

END OF SECTION

City of Palo Alto 2004 Standards Documents and Specifications
Street Tree Verification of Protection, PWS, Section 3.03

Revised 08/06

Table 2-2 Palo Alto Tree Technical Manual

ARBORIST INSPECTION SCHEDULE

All Checked Items Apply to this project:

1. ☒ **Inspection of Protective Tree Fencing.** The Street Tree Verification Form shall be signed by the City Arborist. For other Protected Trees, the project arborist shall provide a written statement with a photograph verifying that he has conducted a field inspection of the trees and that the protective tree fencing is in place prior to issuance of a demolition, grading, or building permit. (see Verification of Tree Protection, Section 1.139).
2. ☐ **Pre-Construction Meeting.** Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading equipment operators, project arborist, City Arborist, and, if a City installed irrigation system exists, the Parks Manager. (Contact 650-496-6962).
3. ☐ **Inspection of Rough Grading.** The project arborist shall perform an inspection during the course of rough grading adjacent to the TPZ to ensure trees will not be injured by compaction, cut or fill, drainage and trenching, and if required, insect neration systems, tree wells, drains and special paving. The contractor shall provide the project arborist at least 48 hours advance notice of such activity.
4. ☐ **Monthly Inspections.** The project arborist shall perform a monthly activity inspection to monitor and advise for conditions and tree health. The City Arborist shall be in receipt of the activity report during the first week of each calendar month, or immediately if there are any revisions to the approved plans or protection measures. Fax to (650) 329-2154. (see Monthly Inspection Report, Section 1.17).
5. ☐ **Special activity within the Tree Protection Zone.** Work in this area (TPZ - described in #7 below) requires the direct onsite supervision of the project arborist (see Trenching, Excavation and Erection, TTM Section 2.20 C).
6. ☐ **Landscape Architect Inspection.** For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the landscape architect to perform a site inspection of all plant stock, quality of the materials and planting (see Quality, Section 5.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The City shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.
7. ☐ **Other** (please describe)

	<h2 style="margin: 0;">City of Palo Alto</h2> <p style="margin: 0;">Tree Department Public Works Department PO Box 10209 Palo Alto, CA 94303 (650)460-5903 FAX: (650)832-5089 inspection@CityOfPaloAlto.org</p>	<h2 style="margin: 0;">Verification of Street Tree Removal</h2>
<p><i>Applicant Instructions: Complete upper portion of this form. Mail or FAX this form along with signed Tree Disclosure Statement to Public Works Dept. Public Works Tree Staff will inspect and notify applicant.</i></p>		
<p>APPLICANT DATE:</p>		
<p>ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED:</p>		
<p>APPLICANT'S NAME:</p>		
<p>APPLICANT'S ADDRESS:</p>		
<p>APPLICANT'S TELEPHONE & FAX NUMBERS:</p>		
<p><i>This section to be filled out by City Tree Staff</i></p>		
<p>1. The Street Trees at the above address(es) are adequately protected. The type of protection used is:</p>	<p>YES <input type="checkbox"/> NO <input type="checkbox"/></p> <p style="text-align: center;">* If NO, go to #2 below</p>	
<p>Inspected by:</p>		
<p>Date of Inspection:</p>		
<p>2. The Street Trees at the above address are <u>NOT</u> adequately protected. The following modifications are required:</p> <p style="margin-top: 20px;">Indicate how the required modifications were communicated to the applicant.</p>		
<p>Subsequent Inspection</p>		
<p>Street trees at above address were found to be adequately protected:</p>	<p>YES <input type="checkbox"/> NO <input type="checkbox"/></p> <p style="text-align: center;">* If NO, indicate in "Notes" below the disposition of cases.</p>	
<p>Inspected by:</p>		
<p>Date of Inspection:</p>		
<p>Notes: List City street trees by species, size, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.</p>		

Return approved sheet to Applicant for demolition or building permit issuance.

8/PWOCF03/TreeRem03B/TreeProtect
01/17/08

---WARNING---
Tree Protection Zone

**This fencing shall not be removed without
City Arborist approval (650-496-5953)**


**Removal without permission is
subject to a \$500 fine per day***

****Palo Alto Municipal Code Section 8.10.110***

City of Palo Alto Tree Protection Instructions are located at <http://www.city.palo-alto.ca.us/trees/technical-manual.html>

City of Palo Alto

200 Hamilton Avenue, Palo Alto, CA 94301




Search:

[Advanced](#)

[Browse By Topic](#)

Home

- [Planning & Community Engagement](#)



Tree Technical Manual

To purchase the Tree Technical Manual

June, 2001 First Edition

View by section:

- Table of Contents (PDF, 67KB)
- Intent and Purpose (PDF, 105MB)
- Introduction - Use of Manual (PDF, 1.03MB)
- Section 1.0 - Definitions (PDF, 96KB)
- Section 2.0 - Protection of Trees During Construction (PDF, 299KB)
- Section 3.0 - Removal, Replacement, and Planting of Trees (PDF, 117KB)
- Section 4.0 - Hazardous Trees (PDF, 105KB)
- Section 5.0 - Tree Maintenance Guidelines (PDF, 110KB)
- Section 6.0 - Tree Reports (PDF, 84KB)

Frequently Asked Questions

- [Home](#)
- [City-owned Trees](#)
- [Privately-owned Trees](#)
- [About the Tree Ordinance](#)
- [Title 8.10](#)
- [Heritage Trees](#)
- [Forms](#)
- [Tree Technical Manual](#)
- [FAQs](#)
- [Contact Us](#)
- [Resources](#)

View All sections:

- Tree Technical Manual - Full (PDF, 1.84MB)

APPENDICES

- Palo Alto Municipal Code Chapter 8.10, Tree Preservation & Management Regulations
- Tree City - USA
- ISA Hazard Evaluation Form
- List of Inherent Fatal Pathogens for Selected Species (Reference source)
- E: ISA Tree Pruning Guidelines (PDF, 1.89MB)
- F: Tree Care Safety Standards, ANSI Z12.1-1-1994 (Reference source)
- G: Pruning Performance Standards, ANSI A300-1995 (Reference source) H:
- Tree Planting Details, Diagram 504 & 505
- I: Tree Disclosure Statement
- J: Palo Alto Standard Tree Protection Instructions

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.** For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.



ARBOR RESOURCES
professional consulting arborists and tree care

TREE PROTECTION REPORT

660 UNIVERSITY AVENUE
PALO ALTO, CALIFORNIA
(511 BYRON ST., 660 & 680 UNIVERSITY AVE.)

Submitted to:

Smith Development
682 Villa Street, Suite G
Mountain View, CA 94041

Prepared by:

David L. Babby
Registered Consulting Arborist® #399
Board-Certified Master Arborist® #WE-4001B

November 19, 2021

p.o. box 25295, san mateo, california 94402 • email: arborresources@comcast.net
office: 650.654.3351 • cell: 650.274.3656 • licensed contractor #796763

David L. Babby, Registered Consulting Arborist® November 19, 2021

3.0 REGULATED TREES

The PAMC regulates specific types of trees on public and private property for the purpose of avoiding their removal or disfigurement without first being reviewed and permitted by the CPA. Three categories within the status of regulated trees include protected trees (PAMC 8.10), street trees (PAMC 8.04.020) and designated trees. Additional Information regarding regulated trees can be viewed on page xiii of the City's *Tree Technical Manual*.

One tree, #10, is defined as a protected tree due to being a coast live oak with a trunk diameter of 50 inches (the threshold for coast live oaks is having a trunk diameters of ≥11.5 inches at 54 inches above grade).

Trees #1 thru 9 are situated within the public right-of-way and defined as street trees.

The designated tree category may apply to a select number of existing trees planted on a commercial or planned development site, for either designated tree landscape or to mitigate tree removal. This category can be enacted by the CPA and applied to any specific tree associated with a proposed development. In the event the City qualifies a specific tree to this category, it may become provisioned to be saved and protected.

660 University Avenue, Palo Alto Smith Development Page 5 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

1.0 INTRODUCTION

Smith Development is planning to construct a mixed-use, four-story building and two levels of underground parking on three properties¹ aligning the southeast side of University Avenue, between Middlefield Road and Byron Street; the project is titled 660 University Avenue. Two existing buildings and a surface parking lot currently occupy the site and will be demolished. As part of their planning submittal, Smith Development has retained me to prepare this *Tree Protection Report*, and specific tasks assigned to execute are as follows:

- Visit the site on 1/16/21 and 11/9/21 to identify 25 trees which have trunks located within the subject property, along the street frontages up to 30 feet from the property boundaries, and on adjoining properties within close proximity to the boundary.
- Determine each tree's trunk diameter pursuant to the City's *Tree Technical Manual*² and the *Guide for Plant Appraisal, 10th Edition*³; all diameters represent inches and are rounded to the nearest whole number.
- Estimate each tree's height and average canopy spread (rounded to the nearest fifth).
- Ascertain each tree's health, structural integrity and form, and assign an overall condition rating (e.g. good, fair, poor or dead).
- Rate each tree's suitability for preservation (e.g. high, moderate or low).
- Obtain photographs; see Exhibit C.
- Assign numbers in a sequential pattern from #1 thru 25, and plot on the site map in Exhibit B (base map is a copy of the *Topographic & Boundary Survey* prepared by BKF and dated 2/17/21).
- Affix round metal tags with corresponding, engraved numbers onto the trunks of onsite and street trees (i.e. all but #10).
- Identify which are defined by the PAMC as protected and/or street trees.
- Review the preliminary architectural plans, dated 9/7/21, to ascertain the potential tree disposition and potential impacts.
- Provide preliminary design guidelines and protection measures to help avoid or mitigate potential impacts to retained trees, as well as conform with City requirements.
- Prepare a written report presenting the above information, and submit via email as a PDF document.

¹ The three property addresses include 511 Byron Street, 660 and 680 University Avenue.
² Available for viewing at www.cityofpaloalto.org/civica/files/sharedassets/BioRadP-8436.
³ Authored by the Council of Tree & Landscape Appraisers, and published by the International Society of Arboriculture (ISA).

660 University Avenue, Palo Alto Smith Development Page 1 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

4.0 SUITABILITY FOR TREE PRESERVATION

Each tree has been assigned either a high, moderate or low suitability for preservation rating as a means to cumulatively measure its health, structural integrity, anticipated life span, remaining life expectancy, location, size, particular species, tolerance to construction impacts, growing space, and safety to property and persons within striking distance. Descriptions of these ratings are presented below, and the high category comprises 1 tree (4%), the moderate category 15 (or 60%), and the low category 10 (or 16%).

High:

Applies to #10.

This coast live oak appears healthy and structurally stable; has no obvious, significant health issues or structural defects; presents a good potential for contributing long-term to the site; and requires only periodic or regular care and monitoring to maintain its longevity and structural integrity.

Moderate:

Applies to #1-3, 7, 8, 11 and 12-25.

These trees contribute to the site, but at levels less than those assigned a high suitability; might have health and/or structural issues which may or may not be reasonably addressed and properly mitigated; and frequent care is typically required for their remaining lifespan.

Low:

Applies to #4-6, 9, 10, and 12-16.

These trees have significant health and/or structural issues expected to worsen regardless of tree care measures employed (i.e. beyond likely recovery). As a general guideline, they should be removed regardless of future site improvements, and any which are retained require frequent monitoring and care throughout their remaining lifespans to minimize risk to any persons or property within striking distance.

660 University Avenue, Palo Alto Smith Development Page 6 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

2.0 TREE DESCRIPTION

Twenty-five (25) trees of 11 various species were inventoried for this report. They are sequentially numbered as 1 thru 25, and the table below identifies their common names, assigned numbers, counts and overall percentages.

Table 1 - Tree Count and Composition

NAME	TREE NUMBER(S)	COUNT	% OF TOTAL
Chinese pistache	8	1	4%
Coast live oak	10	1	4%
Crape myrtle	19 thru 24	6	24%
European hackberry	1	1	4%
Glossy privet	4 & 5	2	8%
London plane tree	2, 3 & 6	3	12%
Olive tree	11	1	4%
Purple Robe locust	17 & 18	2	8%
Raywood ash	12 thru 16	5	20%
Southern magnolia	7 & 9	2	8%
Yew pine	25	1	4%
Total		25	100%

Specific information regarding each tree is presented within the table in Exhibit A. The trees' assigned numbers and approximate locations can be viewed on the site map in Exhibit B, and photographs are presented in Exhibit C.

660 University Avenue, Palo Alto Smith Development Page 2 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

5.0 REVIEW OF POTENTIAL IMPACTS

Implementing the proposed design requires removing trees #11 thru 25 (15 in total) due to being within the building and parking garage footprint. Each represents a relatively small, non-native tree assigned either a low or moderate suitability for preservation.

I also recommend street trees #4 thru 6 are planned for removal due to being in very poor overall condition and assigned a low suitability for preservation; note that because they are publicly-owned street trees, the decision for their removal lies with the CPA. Trees #4 and 5 are relatively small privets with advanced and extensive decline and decay. Tree #6 is a partially uprooted London plane leaning towards the street, and opposite the lean, it has a pronounced buttress root causing extensive and somewhat dramatic hardscape damage. The replacement of these deficient trees will provide the opportunity to significantly improve the future, long-term tree landscape for the site and public.

Trees anticipated for retention include #1-3 and 7-10. Street trees include #1-3 and 7-9, and consider their protection zones as being from their trunks and up to the existing back of sidewalks and street curbs, and 10 feet in all other directions. For those aligning the project site, namely #1-3, 7 and 8, pruning of their canopies will be needed to accommodate shoring installation and constructing the building. My site assessment reveals the trees would not be adversely impacted provided pruning is judiciously performed through limited and highly-selective cuts by a California State licensed tree-service company approved by the CPA.

For #10, the neighboring oak of protected tree status, the architectural design substantially conforms to setbacks provided in January 2021, which stipulates a minimum 30-foot setback from oak's trunk for the future building and parking garage, and a minimum setback of 20 feet for all ground disturbance beneath the existing asphalt surface. The garage and upper building floors are set a few or more feet inside, but careful shoring placement (for driving piles or a drill rig) and pruning can limit impacts.

The 30-foot setback from #10's trunk considers an additional 5 feet towards the tree where pruning would occur for building, scaffolding, manlift clearance, and any shoring

660 University Avenue, Palo Alto Smith Development Page 7 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

Nine (9) trees, #1 thru 9, have trunks within the public right-of-way and are defined and regulated by the PAMC as street trees. Tree #1 aligns Middlefield Road, #2 thru 6 align University Avenue, and #7 thru 9 align Byron Street. Of these, #1 thru 8 are along the street frontage of the project site, whereas #9 is along the frontage of the neighboring southeastern property (and included to conform with CPA report standards).

Tree #10 is located offsite in close proximity to the property boundary. Trees #11 thru 25 have trunks situated within the property.

Two (2) trees, #9 and 19, are not shown on the topo survey. I have added their locations onto the map in Exhibit B, but note those represent only roughly approximate locations and should not be construed as being surveyed.

Trees #1-9 and 11-25 are considered ornamentals and not native to the local region. Tree #10, coast live oak, is native and represents the largest, most visible tree inventoried for this project.

Tree #10 (coast live oak)

Tree #10 is the one inventoried tree defined by the CPA as a protected tree (refer to Section 3.0 in this report for additional information). Its trunk diameter is 50 inches⁴ at 54 inches above soil grade, is an estimated 60 feet tall, and has a mostly balanced canopy spreading nearly 90 feet across.

As part of the initial site study, Smith Development retained me in January 2021 to evaluate #10's condition, as well as provide development setbacks to adequately protect its root zone and canopy while achieving a reasonable assurance of survival, structural integrity and form. A summary of additional observations obtained on 1/16/21 follows, and photos obtained then can be observed in Exhibit B (page C-3). Information regarding my recommended setbacks and review of potential impacts are presented in Section 5.0.

⁴ The diameter represents an approximation using a Biltmore stick.

660 University Avenue, Palo Alto Smith Development Page 3 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

equipment (if applicable). Sections of the canopy requiring pruning to achieve this clearance include a low, 17-inch diameter limb overhanging the lot; an 8-inch diameter branch emerging from a 14-inch diameter limb growing mostly upright at a slight westerly angle; and roughly a dozen smaller branches ranging in size from 1 to 6 inches in diameter. In total, pruning needed would favorably account for only 15-percent of the total canopy, and the tree's form would remain intact.

The 20-foot setback from #10's trunk for ground disturbance applies to any soil compaction, grading, subexcavation, overexcavation, trenching, drilling/auguring, storm drains, swales, etc. Also, the option to remove the existing asphalt surface and establish a planter area within the 20-foot buffer could benefit the oak's root zone; however, digging into existing base material might damage significant roots (and would require further discussion, review and consideration).

Protection for retained street trees #1-3, 7 and 8 should include what the CPA defines as Type III Protection (aka trunk wrap), plus plywood to cover unpaved ground (i.e. planters) within their TPZ. Chain link panels could also be utilized in lieu, or combination of, plywood. For #10, protection would consist of CPA Type I Protection (aka chain link mounted on driven posts).

Additional and more defined mitigation measures are presented within the next section of this report. They should be incorporated into project plans, carefully followed throughout the entire demolition, grading and construction processes, and are subject to revision upon reviewing any revised or future project plans.

660 University Avenue, Palo Alto Smith Development Page 8 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

Overall, the oak appears viable and healthy, and exhibits no symptoms or signs of being infected or infested by harmful pathogens. Shoot growth, color and density appear typical for a coast live oak, and woundwood has favorably closed off the vast majority of prior wounds.

Existing features beneath its canopy and surrounding the trunk appear dated, and based on its generally healthy condition, I conclude the tree has adapted well to current site and growing conditions. Its base is buried by leaf debris, and is situated roughly 6 inches or less from a 2-foot tall wall. Northeast of its trunk is barren soil, surface roots, and a raised deck which nears 2 feet above grade and serves as a walkway. Towards the southwest, this walkway continues by nearly 30 feet from the trunk, steadily descending and serving as an ADA ramp leading to the neighbor's parking lot.

Beneath the section of canopy overhanging the project site is an asphalt parking lot elevated above original grade by roughly 2 feet. There are no signs of roots forming cracks or mounds of the asphalt surface; however, given the dated age of the wall and surrounding features, I suspect roots are present, but highly limited as compared to the more favorable root-growing conditions on the neighboring property. A parking lot medium, particularly as elevated as this one, is quite unsuitable for promoting root growth, and the retaining wall footing (depth unknown) also contributes towards deflecting root growth away from the parking lot.

Its structure also appears intact and stable, consisting of a main trunk dividing into five leaders at 10 feet high; the unions of these are favorably spaced apart, although visual and manual examination of the junction should occur once neighboring site access can be obtained to identify the presence of any defects, or lack thereof. The section of trunk and root collar buried by leaf debris should also be examined at that time.

The canopy is highly elevated above the parking lot and neighboring site, appears to be regularly maintained over its many years (and no immediate pruning items were found). The elevated canopy, however, does unfavorably displace limb and branch weight towards the canopy's edges, and potentially increases the possibility of limb and branch failure (although the regular maintenance provided certainly helps minimize this risk).

660 University Avenue, Palo Alto Smith Development Page 4 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

6.0 TREE PROTECTION MEASURES

Recommendations presented within this section are based on my review of the preliminary architectural plans, and serve as measures to help mitigate or avoid impacts to trees anticipated for retention. I (hereinafter, "project arborist") should be consulted in the event any cannot be feasibly implemented. Please note, unless otherwise stated, all referenced distances from trunks are intended to be from the closest edge, face of, their outer perimeter at soil grade.

6.1 Design Guidelines

- Consider each Tree Protection Zone (TPZ) as those minimum distances specified within Section 5.0 of this report. The TPZ is the area where the following minimum activities should be avoided: trenching, soil scraping, compaction, mass and finish-grading, overexcavation, subexcavation, tilling, ripping, swales, bio-swales, storm drains, dissipaters, equipment cleaning, removal of underground utilities and vaults, altering existing water/drainage flows, stockpiling and dumping of materials, and equipment and vehicle operation. Where an impact encroaches slightly within a setback, it can be reviewed on a case-by-case basis by the project arborist to determine appropriate mitigation measures.
- The CPA requires all design changes occurring near retained trees are reviewed by the project arborist prior to resubmitting plans, for purposes of identifying potential impacts and any possible mitigation measures.
- Per City requirements, incorporate this report into the project plan set, following the CPA T-1 sheet, and copying onto T-2, T-3, etc. until its entirety is shown (and in a manner which all report text can be clearly read on the plan sheets).
- On all architectural, civil, landscape and electrical site-related plans, show the trunk locations, trunk diameters (as circles to scale), and assigned numbers of all inventoried trees (see map in Exhibit B). Also, add notes instructing contractors to comply with recommendations presented in this report and on Sheet T-1, and to contact the project arborist prior to permitted work being performed within a TPZ.

660 University Avenue, Palo Alto Smith Development Page 9 of 16

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE
ARBORIST REPORT

SCALE

SHEET NUMBER

T-2



All other tree-related reports shall be added to the space provided on this sheet (adding as needed). Include this sheet(s) on Project Sheet Index or Legend Page. A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet
City of Palo Alto



T-2

L 4.3

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**

For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.

David L. Babby, Registered Consulting Arborist® November 19, 2021

- On a tree disposition plan or tree protection plan (or equivalent), include the following: the above notes, identify which trees are proposed for removal by placing an "X" across their trunks, and identify the Tree Protection Zones and protection fencing types as shown on the map in Exhibit B.
- Abandon any underground portions of existing and unused lines, pipes and manholes, etc. within a TPZ (prescribe they are cut off at existing soil grade versus being dug up and causing root damage); add this provision onto the demolition plan.
- Route underground utilities and services beyond TPZs, and per CPA guidelines for street trees, establish at least 10 feet from their trunks. Where this is not feasible, consider the following alternative trenching or installation methods (listed in order of least to most impactful): directionally bore by at least 3.5 to 4 feet below grade, tunnel using a pneumatic air device (e.g. an AirSpade®), or manually dig with a shovel (i.e. no jackhammer); these assume pipe bursting, an optimal method, does not apply to this project. For boring, establish access pits and above-ground infrastructure (e.g. splice boxes, meters and vaults) beyond TPZs.
- Where within 30 feet from #10's trunk, ensure specifications by the geotechnical, soils and structural engineers do not require compaction, overexcavation, subexcavation or fill beyond 2 feet from the parking garage wall (towards the tree) and 5 feet beyond the building's foundation. Shoring utilized to achieve these setbacks, such as a pile driver or drill rig, shall not be used where significant damage to a tree's canopy would occur (can be determined on a case-by-case basis).
- Any new walkway or sidewalk proposed on existing unpaved ground within a TPZ should be designed and built entirely above existing soil grade and surface roots (i.e. a no-dig design), including for base material, edging and forms. Also, direct compaction of soil shall be avoided (levels comparable to foot-tamping are acceptable), and soil fill used to level the top of walk to existing grade should not exceed 18 to 24 inches from a walk's edge, not be compacted, nor placed closer than 10 feet from a tree's trunk. Tensar® BX Geogrid (www.tensarcorp.com) is a material which can help address these limited excavation and compaction requirements.

660 University Avenue, Palo Alto
Smith Development Page 10 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

- Spools generated during demolition, excavation and trenching must not be piled or spread over unpaved ground within a TPZ. If necessary, temporarily pile on existing concrete, plywood or a tarp.
- Any authorized digging within a TPZ should retain and protect roots encountered with diameters of ≥2 inches. Once exposed, cover with wet burlap and keep continually moist until they can be assessed by the project arborist; note that roots of street trees must be evaluated by the CPA arborist prior to severing. If authorized by the project arborist and/or CPA arborist for cutting, cleanly sever at 90° to the angle of root growth against the cut line using sharp tools (e.g. loppers or handaws), and then immediately after, the cut end shall be either buried with soil or kept continually moist by burlap until the dug area is backfilled. Roots encountered with diameters less than the 2-inch threshold can be cleanly severed at a 90° angle to the direction of root growth.
- All electrical and irrigation routes shall be staked, reviewed and approved by the project arborist prior to trenching occurring within a TPZ.
- Avoid using tree trunks as winch supports for moving or lifting heavy loads, or for tying rope, cables, chains, signs or other items around.
- Dust accumulating on trunks and canopies during dry weather periods may need to be periodically washed away (e.g. every three to four months).
- Where beneath canopies, avoid disposing harmful products (such as cement, paint, chemicals, oil and gasoline) anywhere on site that allows drainage within or near TPZs; do not wash any equipment; and avoid applying herbicides (if applied, they should be labeled for safe use near trees). Liming shall not occur within 50 feet from a trunk.

660 University Avenue, Palo Alto
Smith Development Page 13 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

- For any retaining or landscape wall within a TPZ, utilize a pier and above-grade beam system, establish the beam spanning between footings to be above-grade (i.e. no-dig design except for footings), and avoid fill and compaction between footings.
- Design any new bioswales, storm drains and swales well-beyond TPZs.
- The permanent and temporary drainage design, including downspouts, should require water being discharged beneath #10's canopy.
- All electrical routes should be designed and represented on the electrical site plan to be beyond TPZs.
- Any new light poles should be established beyond tree canopies, or at a minimum only where minor branch clearance is needed. The proximity of tree trunks should also be considered, and placed as far from them as possible.
- The future staging area and route(s) of access should be shown on the final site plan and avoided on unpaved areas beneath or near canopies.
- The erosion control design should represent silt fence and/or straw rolls at location beyond TPZs, and at a minimum, not against a tree's trunk. Where within a TPZ, if material should not be embedded into the ground by more than 2 inches, nor require the severance of surface or shallow roots.
- Avoid specifying the use of herbicides use within a TPZ; where used on site, they should be labeled for safe use near trees. Also, liming shall not occur or be prescribed within 50 feet from a tree.
- The landscape design should conform to the following additional guidelines:
 - Tilling, ripping, surface scraping and compaction within TPZs should be avoided.
 - Irrigation should not strike within 12 inches from trunks of existing trees, nor applied against trunks of new trees.
 - Plant material installed beneath tree canopies should be ≥12 to 24 inches from their trunks.

660 University Avenue, Palo Alto
Smith Development Page 11 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

7.0 ASSUMPTIONS AND LIMITING CONDITIONS

- All information presented herein covers only the inventoried trees listed in Exhibit A, a reflects their size, condition, and areas viewed from the project site and adjoining streets a sidewalk on 1/16/21 (for oak #10 and 11/9/21 for all others). I hold no opinion towards all trees on or surrounding the project area.
- The documented condition and suitability ratings of dominant trees are subject to change or they can be observed following their annual regrowth of leaves.
- Observations were performed visually from the ground without probing, coring, dissecting excavating.
- I cannot provide a guarantee or warranty, expressed or implied, that deficiencies or problems any trees or property in question may not arise in the future.
- No assurance can be offered that if all my recommendations and precautionary measures (verbal or in writing) are accepted and followed, that the desired results may be achieved.
- I cannot guarantee or be responsible for the accuracy of information provided by others.
- I assume no responsibility for the means and methods used by any person or company implementing the recommendations provided in this report.
- The information provided herein represents my opinion. Accordingly, my fee is in no way contingent upon the reporting of a specified finding, conclusion or value.
- Numbers shown on the site map in Exhibit B are solely intended to represent a tree's rough approximate location and should not be construed as surveyed points.
- This report is proprietary to me and may not be copied or reproduced in whole or part without prior written consent. It has been prepared for the sole and exclusive use of the parties to whom submitted for the purpose of contracting services provided by David L. Babby.
- If any part of this report or copy thereof be lost or altered, the entire evaluation shall be invalid.

Prepared By: 
David L. Babby
Registered Consulting Arborist® #399
Board-Certified Master Arborist® #WE-40018
CA Licensed Tree Service Contractor #796763 (CG/D49)

Date: November 19, 2021

660 University Avenue, Palo Alto
Smith Development Page 16 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

- New street tree(s) should be designed to be at least 10 feet from any existing or new utility (per CPA guidelines).
- All new trees should be installed, including necessary irrigation, by an experienced California state-licensed landscape contractor (C-27) or tree service company (D-49), and performed to professional industry standards. Only if necessary to stand upright, they should be double-staked (no cross-brace) with rubber tree ties or equivalent, and the support stakes cut below the first main lateral branch. All nursery stakes shall be removed. Root crowns of new trees shall be visible and absent of encircling roots.
- Irrigation and lighting features (e.g. main line, laterals, valve boxes, wiring and controllers) should not require trenching inside TPZs, including header/lateral lines. In the event this is not feasible, they may require being installed in a radial direction to, and terminate a specific distance from a trunk (versus crossing past it). In certain instances, a pneumatic air device may be needed to avoid root damage, and any Netafun tubing placed on grade.
- Irrigation for new trees should be supplied through an automatic timer, separate from other plant material, and supplied by one to two bubblers (minimum two for a 48-inch box). The bubblers should be placed and staked on the rootball's surface (not against a trunk, in a sleeve or on mulch), at around 1/2 to 1/3 the distance between the trunk and rootball edge. Additionally, an 8-inch tall circular berm formed by soil should be established around a rootball's perimeter, and a 3-inch layer of mulch spread over their tops, kept 1-inch from the trunks' bases.
- Ground cover beneath canopies of existing trees should be comprised of a 3-inch layer of coarse wood chips or other high-quality mulch (gorilla hair, rock, stone, gravel, black plastic or other synthetic ground cover should be avoided). Mulch should keep off the trees' trunks or visible root collars.
- Bender board or other edging material proposed beneath the canopies should be established on top of existing soil grade (such as by using vertical stakes).
- Herbicides should be avoided within a TPZ, and where used on site, labeled for safe use near trees. Liming shall not occur within 50 feet from a trunk.

660 University Avenue, Palo Alto
Smith Development Page 12 of 16

David L. Babby, Registered Consulting Arborist® November 19, 2021

EXHIBIT A: TREE INVENTORY TABLE (four sheets)

ARBOR RESOURCES
professional consulting, arborists and tree care

TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	SIZE			CONDITION					REGULATED		
		Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition	Structural Integrity	Soil/Root Condition	Special Considerations	Recommendation	Proposed for Removal	Protected Tree	Street Tree
1	European hollyhock (<i>Alcea rosea</i>)	20	35	35	60%	40%	70%	Fair	Moderate	-	-	X
Comments: Within a 4' wide planter strip between street and sidewalk. Trunk's base abuts curb. Highly elevated canopy. Sidewalk is slightly raised, new and historically. Columnar leaders emerge at 8' high. Has three large, partial gridding roots, one over a buttress root and can be pruned away.												
2	London plane tree (<i>Platanus × hispanica</i>)	15	55	50	60%	70%	50%	Fair	Moderate	-	-	X
Comments: Becoming dormant. Within a narrow 3' wide by 4.5' long planter. Adjacent sidewalk is raised and has been historically, and adjacent curb is cracked. Asymmetrical canopy with excessive limb weight, and growth towards the building is elongated. Surface root in lawn adjoining sidewalk.												
3	London plane tree (<i>Platanus × hispanica</i>)	14	50	40	60%	70%	70%	Fair	Moderate	-	-	X
Comments: Becoming dormant. Within a 3' wide by 15' long planter. Adjacent sidewalk is cracked at E corner of planter. Surface root in lawn adjoining sidewalk. Vertical form.												
4	Glossy privet (<i>Ligustrum lucidum</i>)	6	15	10	30%	30%	20%	Poor	Low	-	-	X
Comments: Within a 2' wide by 3.5' long planter. Leans NW. Significant decline with deadwood. Prior dominant leader cut at 6' cut, the resulting wound is decaying. Adjacent to light pole. Adjacent concrete raised.												
5	Glossy privet (<i>Ligustrum lucidum</i>)	13	20	20	30%	30%	40%	Poor	Low	-	-	X
Comments: Within a 2' wide by 4' long planter. Adjacent curb is buckled and raised, and adjacent sidewalk has been historically raised at multiple locations. Advanced decline with large deadwood. Large decaying wounds at 6' and 8' high. Asymmetrical canopy.												
6	London plane tree (<i>Platanus × hispanica</i>)	10	45	35	60%	30%	60%	Poor	Low	-	-	X
Comments: Within a 2.5' wide by 3.5' long planter. Has a 16" NW lean, and opposite the lean is a pronounced buttress root. Sidewalk and curb have been historically raised at multiple locations. Columnar top. Asymmetrical canopy with an extended limb over street, as well as a low branch lying on top of #22.												

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #399

1 of 4

November 19, 2021

ARBOR RESOURCES
professional consulting, arborists and tree care

TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	SIZE			CONDITION					REGULATED		
		Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition	Structural Integrity	Soil/Root Condition	Special Considerations	Recommendation	Proposed for Removal	Protected Tree	Street Tree
7	Southern magnolia (<i>Magnolia grandiflora</i>)	21	30	35	40%	50%	50%	Poor	Moderate	-	-	X
Comments: Within a 3.5' wide by 15' long planter. Root crown encompasses entire planter width. Adjacent curb is buckled at multiple locations, including historically. Advanced and extensive decline with large deadwood. Canopy has been reduced in past.												
8	Chinese plane tree (<i>Platanus chinensis</i>)	14	25	35	60%	60%	70%	Fair	Moderate	-	-	X
Comments: At the NW edge of a 2' wide by 9' long planter. Adjacent sidewalk historically raised at multiple locations. Large cuts along canopy's bottom. Low canopy over street, and branches are on roof.												
9	Southern magnolia (<i>Magnolia grandiflora</i>)	20	35	35	20%	30%	30%	Poor	Low	-	-	X
Comments: Along footage of the adjoining SE property, its trunk being nearly 22' from the property's fence. Within a narrow 2.5' wide planter. Trunk is 4' from CPA electrical and PacifiCell vaults. Sidewalk bulks out near trunk. Canopy has been highly elevated, and a large amount of foliage within its lower canopy consists of waterproots (which are rapidly-growing, weakly-attached shoots). Has several large gridding roots over a buttress root. Advanced, extensive decline with deadwood.												
10	Coast live oak (<i>Quercus agrifolia</i>)	50	60	90	70%	40%	50%	Fair	High	-	X	-
Comments: Offsite on the adjoining SE property. Its base is 6" from a 2' tall wall and buried by leaf litter. Trunk divides into 5 leaders at 10' high and are favorably spaced apart. Canopy is highly elevated over the site (existing parking lot).												
11	Office tree (<i>Olea europaea</i>)	8.8	15	10	60%	50%	40%	Poor	Moderate	X	-	-
Comments: Canopy is rounded. Sucker growth has creatively been formed into a shrub surrounding the lower trunk. Trunk bifurcates at 2.5' high and forms a narrow attachment.												
12	Raywood ash (<i>Fraxinus x Raywood</i>)	2	15	10	60%	40%	20%	Poor	Low	X	-	-
Comments: Dormant. Within a square planter in parking lot. Has a mostly one-sided canopy. Trunk bends.												

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #399

2 of 4

November 19, 2021

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE
ARBORIST REPORT

SCALE

SHEET NUMBER

T-2



All other tree-related reports shall be added to the space provided on this sheet (adding as needed). Include this sheet(s) on Project Sheet Index or Legend Page. A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet
City of Palo Alto



T-2

L 4.4

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**

For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual** (TTM) found at www.cityofpaloalto.org/trees/.



TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	SIZE			CONDITION					REGULATED
		Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition (100%-least, 0%-worst)	Structural Integrity (100%-least, 0%-worst)	Form (100%-least, 0%-worst)	Overall Condition (Good/Fair/Poor/Degraded)	Suitability for Preservation (High/Moderate/Low)	
13	Raywood ash (<i>Fraxinus s. 'Raywood'</i>)	12	20	15	30%	30%	30%	Poor	Low	X
Comments: Within a square planter. Trunk bifurcates at 6' high. Significant dieback with deadwood. Adjacent asphalt is cracked and forms a short mound.										
14	Raywood ash (<i>Fraxinus s. 'Raywood'</i>)	11	20	20	40%	30%	30%	Poor	Low	X
Comments: Within a square planter. Has many large decaying cuts. Deadwood. Adjacent asphalt is cracked and slightly raised.										
15	Raywood ash (<i>Fraxinus s. 'Raywood'</i>)	6	15	15	20%	10%	20%	Poor	Low	X
Comments: Within a square planter. Has a large decay column along entire trunk, as well as a large decaying wound at 6' high where a prior leader was cut away. Advanced levels of dieback and deadwood.										
16	Raywood ash (<i>Fraxinus s. 'Raywood'</i>)	15	25	20	20%	20%	20%	Poor	Low	X
Comments: Within a square planter. Has a pronounced L lean. Low limb overhangs adjacent parking space. Significant decay throughout, including along trunk. Deadwood. Adjacent asphalt forms a mound.										
17	Purple Robe locust (<i>Robinia 'Purple Robe'</i>)	6	35	20	60%	40%	60%	Fair	Moderate	X
Comments: Dormant. Has a single support stake which is no longer necessary and should be removed.										
18	Purple Robe locust (<i>Robinia 'Purple Robe'</i>)	5	25	20	60%	40%	30%	Poor	Moderate	X
Comments: Dormant. Has a single support stake which is no longer necessary and should be removed. Excessive limb weight overhanging parking lot. Asymmetrical form away from #17.										
19	Crape myrtle (<i>Lagerstroemia indica</i>)	5	10	10	60%	40%	50%	Fair	Moderate	X
Comments: Within a 2' raised planter. Dormant. Multiple trunks originate 8' high. Canopy is slightly asymmetrical.										

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #339

3 of 4

November 19, 2021



TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	SIZE			CONDITION					REGULATED
		Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition (100%-least, 0%-worst)	Structural Integrity (100%-least, 0%-worst)	Form (100%-least, 0%-worst)	Overall Condition (Good/Fair/Poor/Degraded)	Suitability for Preservation (High/Moderate/Low)	
20	Crape myrtle (<i>Lagerstroemia indica</i>)	3, 3, 2	10	5	60%	40%	50%	Fair	Moderate	X
Comments: Within a 2' raised planter. Dormant. Multiple trunks emerge at grade. Canopy is asymmetrical.										
21	Crape myrtle (<i>Lagerstroemia indica</i>)	6	15	10	60%	40%	50%	Fair	Moderate	X
Comments: Within a 2' raised planter. Dormant. Multiple trunks originate 6' high. Canopy is slightly asymmetrical.										
22	Crape myrtle (<i>Lagerstroemia indica</i>)	6	15	10	60%	40%	50%	Fair	Moderate	X
Comments: Within a 2' raised planter. Dormant. Multiple trunks originate 5' high. Canopy is slightly asymmetrical. A low limb of #6 is on top of its canopy.										
23	Crape myrtle (<i>Lagerstroemia indica</i>)	6	15	10	60%	40%	60%	Fair	Moderate	X
Comments: Within a 2' raised planter. Dormant. Multiple trunks originate 5' high. Canopy is slightly asymmetrical.										
24	Crape myrtle (<i>Lagerstroemia indica</i>)	4, 3, 2	15	10	60%	40%	60%	Fair	Moderate	X
Comments: Within a 2' raised planter. Dormant. Multiple trunks emerge at grade. Canopy is asymmetrical.										
25	Yew pine (<i>Podocarpus macrophyllus</i>)	8	10	10	60%	40%	30%	Poor	Moderate	X
Comments: Immediately adjacent to building. Shrub form and shaped into a cube. Trunk bifurcates at 3' high.										

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #339

4 of 4

November 19, 2021

David L. Babby, Registered Consulting Arborist®

November 19, 2021

EXHIBIT B:

SITE MAP

(one sheet)




EXHIBIT C:

PHOTOGRAPHS

(five sheets)

Photo Index

Page C-1: Trees #1 thru 6

Page C-4: Trees #11 thru 18

Page C-2: Trees #7 thru 9

Page C-5: Trees #19 thru 25

Page C-3: Tree #10

660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®

November 19, 2021



660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®

November 19, 2021



660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®

November 19, 2021



660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®

November 19, 2021



660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®

November 19, 2021



660 University Avenue, Palo Alto
Smith Development

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
1	12/01/21	PLANNING SUBMITTAL
2	05/13/22	PLANNING RESUBMITTAL #1
3	08/15/22	PLANNING RESUBMITTAL #2
4	11/02/22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE
ARBORIST REPORT

SCALE

SHEET NUMBER

T-2



All other tree-related reports shall be added to the space provided on this sheet (adding as needed). Include this sheet(s) on Project Sheet Index or Legend Page. A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet
City of Palo Alto




T-2

L 4.5


**660 UNIVERSITY AVENUE
EXISTING CONDITIONS AND DEMOLITION PLAN**

Date	12/01/2021	No.	Revisions
Scale	1" = 10'	1	PLANNING RESUBMITTAL #1 05.13.2022
Design	MS	2	PLANNING RESUBMITTAL #2 08.15.2022
Drawn	TKI	3	PLANNING RESUBMITTAL #3 11.02.2022
Approved	TRM		
Job No	20212113		

SD1.0



- NOTES:**
1. DEACTIVATION AND REMOVAL OF GAS AND ELECTRIC LINES TO BE COORDINATED WITH CPAU PRIOR TO DEMOLITION.
 2. SERVICE DISCONNECTION REQUIREMENT: WATER, GAS, AND ELECTRIC SERVICES AND METERS MUST BE DISCONNECTED WHENEVER A CONTRACTOR IS PLANNING FOR COMPLETE/PARTIAL BUILDING DEMOLITION OR ANY EXCAVATION. WHERE TO APPLY FOR SERVICE DISCONNECTION: THE APPLICANT SHALL FIRST SUBMIT AN "APPLICATION FOR UTILITIES DISCONNECTION PRIOR TO BUILDING DEMOLITION/REMODELING" INCLUDING A SIGNED "DECLARATION CONCERNING TENANCY OF BUILDING" TO CITY OF PALO ALTO UTILITIES CUSTOMER SERVICE CENTER 250 HAMILTON AVE. (CITY HALL) GROUND FLOOR, PALO ALTO, CA 94301. TELEPHONE (650) 329-2161. FORMS ARE AVAILABLE ONLINE.
 3. STATEMENT: THE ELEVATIONS SHOWN ON THIS SURVEY ARE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88), U.S. SURVEY FEET, PER A LEVEL LOOP PERFORMED BY BKF ON JANUARY 23, 2021 FROM CITY OF PALO ALTO BENCHMARK NO. 2189, A CHISELED SQUARE AT THE NORTHWESTERLY CORNER OF THE NORTHEAST CURB RETURN AT THE INTERSECTION OF BYRON STREET AND HAMILTON AVENUE, HAVING A PUBLISHED ELEVATION OF 40.73' (NGVD 29), AND APPLYING A CONVERSION FACTOR (FROM NGVD 29 TO NAVD 88) OF +2.75 FEET AS DIRECTED BY THE CITY OF PALO ALTO. ELEVATION = 43.48'





CALIFORNIA

660 UNIVERSITY AVENUE SITE PLAN



SANTA CLARA COUNTY

CITY OF PALO ALTO

Date	12/01/2021	No.	Revisions
Scale	1" = 10'	1	PLANNING RESUBMITTAL #1 05.13.2022
Design		2	PLANNING RESUBMITTAL #2 06.15.2022
Drawn	TKI	3	PLANNING RESUBMITTAL #3 11.02.2022
Approved	TRM		
Job No	2021213		

Drawing Number:

SD2.0



LEGEND:



TC X.X X EXISTING GRADE
FL X.X X PROPOSED GRADE
----- GRADE BREAK

ABBREVIATIONS:

BFE BASE FLOOD ELEVATION
BOW BOTTOM OF WALL
BS BOTTOM OF STEP
BW BACK OF WALK
EG EXISTING GRADE
FF FINISHED FLOOR
FG FINISHED GRADE
FL FLOW LINE
GD GROUND
TC TOP OF CURB
TOW TOP OF WALL
TS TOP OF STEP

NOTE:

1. BASE FLOOD ELEVATION (BFE) FOR PROJECT SITE IS 47. PROPOSED FINISHED FLOOR IS 1 FOOT ABOVE BFE, PLUS APPROXIMATELY 2 INCHES TO ACCOUNT FOR CONSTRUCTION TOLERANCE.



660 UNIVERSITY AVENUE
GRADING PLAN

CITY OF PALO ALTO

SANTA CLARA COUNTY

CALIFORNIA

255 SHORELINE DRIVE
SUITE 200
PALO ALTO, CA 94301
(650) 492-1300
www.bkf.com



Revisions		No.	Date
1	PLANNING RESUBMITTAL #1	05.13.2022	
2	PLANNING RESUBMITTAL #2	08.15.2022	
3	PLANNING RESUBMITTAL #3	11.02.2022	
Design	MS		
Drawn	TKI		
Approved	TRM		
Job No	20212113		

Drawing Number:


SD3.0

- LEGEND:**
- PROPERTY LINE
 - ADJACENT PROPERTY LINE
 - EX FENCE
 - EX SANITARY SEWER LINE
 - EX STORM DRAIN LINE
 - EX DOMESTIC WATER LINE
 - EX COMMUNICATIONS LINE
 - EX OVERHEAD LINE
 - EX GAS LINE
 - EX SANITARY SEWER MANHOLE
 - EX COMMUNICATIONS MANHOLE
 - EX VALVE
 - EX STREET LIGHT
 - EX FIRE HYDRANT

- ABBREVIATIONS:**
- SS PR SANITARY SEWER LINE
 - DW PR STORM DRAIN LINE
 - FW PR DOMESTIC WATER LINE
 - IR PR DOMESTIC WATER LINE
 - LT PR CLEANOUT
 - PR WATER VALVE
 - PR FDC
 - PR MANHOLE

- ABBREVIATIONS:**
- CB CATCH BASIN
 - CO CLEANOUT
 - DW DOMESTIC WATER
 - FDC FIRE DEPARTMENT CONNECTION
 - FW FIRE WATER
 - IRR IRRIGATION
 - LT LATERAL
 - MH MANHOLE
 - RPDA REDUCED PRESSURE DETECTOR ASSEMBLY
 - RPPA REDUCED PRESSURE PRINCIPLE ASSEMBLY
 - SD STORM DRAIN
 - SS SANITARY SEWER
 - WM WATER METER

- NOTES:**
1. RPPA BACKFLOW PREVENTER TO BE LOCATED IN BASEMENT.
 2. RPDA BACKFLOW PREVENTER TO BE LOCATED IN BASEMENT.
 3. STORMWATER BEST MANAGEMENT PRACTICES (BMPs) ASSOCIATED WITH REFUSE MANAGEMENT (INCLUDING ACTIONS RELATED TO REFUSE PICK-UP AND THE ENCLOSURE ITSELF) SHALL BE FOLLOWED TO ENSURE POLLUTION PREVENTION AND PREVENTING POTENTIAL DISCHARGES TO THE CITY'S STORM DRAIN SYSTEM. STORMWATER BMPs INCLUDE, BUT ARE NOT LIMITED TO, POWER WASHING THE PAVEMENT ON BOTH THE PRIVATE PROPERTY AND IN THE RIGHT-OF-WAY AND SIDEWALK A MINIMUM OF ONCE A YEAR BEFORE THE WET SEASON BEGINS ON OCTOBER 1ST; UTILIZING A POWER WASHING CONTRACTOR THAT IS A RECOGNIZED SURFACE CLEANER BY THE BAY AREA STORMWATER MANAGEMENT AGENCIES ASSOCIATION (BASMAA); DISPOSING OF WASH WATER ACCORDING TO THE RECOGNIZED SURFACE CLEANER CERTIFICATION REQUIREMENTS; AND REMOVING ANY POTENTIAL TRASH BUILD-UP ON A REGULAR BASIS.
 4. PER CITY OF PALO ALTO UTILITIES RULES & REGULATION 15 METERING, THE CITY WILL PROVIDE A MASTER METER AT AN APPROVED LOCATION NEAR TO THE PUBLIC WATER MAIN AND RIGHT OF WAY TO SERVE THE WHOLE DEVELOPMENT OR BUILDING. THE MULTIUNIT RESIDENTIAL STRUCTURE MUST COMPLY WITH CALIFORNIA WATER METERING FOR MULTI-UNIT STRUCTURES WATER CODE AS AMENDED BY LAW SENATE BILL 7 (WATER CODE, DIVISION 1, CHAPTER 8, ARTICLE 5, SECTION 537-537.5) THAT REQUIRES INDIVIDUAL WATER METERS OR SUBMETERS FOR EACH UNIT FOR STRUCTURES CONSTRUCTED AFTER JANUARY 1, 2018.
 5. AS DISCUSSED WITH JOHN NGUY ON 08/10/22: PROJECT WILL REUSE EXISTING 4" LATERAL AND CLEANOUT IN BYRON. CONTRACTOR TO PERFORM VIDEO INSPECTION PRIOR TO USE TO DETERMINE IF LATERAL CAN BE REUSED OR NEEDS TO BE REPLACED.



255 SHORELINE DRIVE
SUITE 200
PALO ALTO, CA 94065
(650) 492-6300
www.bkf.com



CALIFORNIA

660 UNIVERSITY AVENUE UTILITY PLAN

SANTA CLARA COUNTY

CITY OF PALO ALTO

Revisions		No.	Date
1	PLANNING RESUBMITTAL #1	05.13.2022	
2	PLANNING RESUBMITTAL #2	08.15.2022	
3	PLANNING RESUBMITTAL #3	11.02.2022	
TRM	Approved	2022113	
Job No			

Drawing Number:

SD4.0

LANDS OF HEIDARI
APN. 120-03-054
(PARCEL ONE)
(DN 21593134)
(LOTS 61 & 62)
(ID MAPS 149)


LANDS OF CHENG & YI
APN. 120-03-045
(DN 20890120)
(LOTS 50 & 51)
(ID MAPS 149)

DRAWING NAME: K:\2021\212113_660_University_Ave\ENG\SD\5_0-Stormwater_Management_Plan.dwg
PLOT DATE: 10-31-22 PLOTTED BY: inou


LEGEND



SELF TREATING/RETAINING AREA



PROPOSED INTERCEPTOR TREE



EXISTING INTERCEPTOR TREE



NOTE:

1. EXISTING TREE CANOPY SHOWN IS APPROXIMATE.

CATCHMENT ID	CATCHMENT AREA	NUMBER OF PROPOSED TREES	PROPOSED TREE CREDIT	EXISTING TREE CREDIT	CATCHMENT AREA W/TREE CREDIT	BIO-RETENTION AREA	TREATMENT AREA	TREATMENT AREA REQUIRED	MEETS REQUIREMENT?
DMA 1	13,351 SF	-	-	-	13,351 SF	1	882 SF	534 SF	YES
DMA 2	2,223 SF	-	-	-	2,223 SF	2	90 SF	88 SF	YES
DMA 3	311 SF	-	-	500 SF	0 SF	N/A	N/A	N/A	N/A
DMA 4	356 SF	-	-	720 SF	0 SF	N/A	N/A	N/A	N/A
DMA 5	779 SF	3	300 SF	634 SF	0 SF	N/A	N/A	N/A	N/A
DMA 6	582 SF	-	-	790 SF	0 SF	N/A	N/A	N/A	N/A
DMA 7*	942 SF	2	200 SF	742 SF	0 SF	N/A	722 SF	371 SF	YES
DMA 8**	741 SF	-	-	-	741 SF	N/A	N/A	N/A	N/A

* DMA 7 DRAINS TO LANDSCAPE AND IS CONSIDERED SELF-TREATING VIA THE 2:1 (IMPERVIOUS:PERVIOUS) RULE PER SANTA CLARA COUNTY C.3 TECHNICAL GUIDANCE.
** WOODEN DECK IS PERVIOUS AND CONSIDERED SELF-TREATING.


STORMWATER QUALITY SIZING SUMMARY




DRAWING NAME: K:\2021\212113_660_University Ave\ENG\SD\SD6_0-Sections.dwg
PLOT DATE: 11-02-22 PLOTTED BY: Inou

ABBREVIATIONS:


C&G CURB AND GUTTER
L/S LANDSCAPE
S/W SIDEWALK




SECTION A
NOT TO SCALE



SECTION B
NOT TO SCALE




SECTION C
NOT TO SCALE




Date		No.		Revisions	
12/01/2021	1	10'	1	PLANNING RESUBMITTAL #1	05.13.2022
	2	MS	2	PLANNING RESUBMITTAL #2	08.15.2022
	3	TKI	3	PLANNING RESUBMITTAL #3	11.02.2022
	TRM				
	Job No				20212113
Drawing Number:					





1
-
4' WATER METER
NOT TO SCALE



2
-
COMBINED WATER METER
NOT TO SCALE

Revisions	
No.	Date
1	12/01/2021
2	08/15/2022
3	11/02/2022

Scale	1" = 10'
Design	MS
Drawn	TKI
Approved	TRM
Job No	20212113


Drawing Number: SD7.1


660 UNIVERSITY AVENUE
DETAILS

CITY OF PALO ALTO

SANTA CLARA COUNTY

CALIFORNIA





WORK RESPONSIBILITY JOINT TRENCH

TRENCHING EXCAVATE & BACKFILL.....	<input type="radio"/> CPAU ELECTRIC <input type="radio"/> CPAU GAS <input type="radio"/> TELEPHONE <input type="radio"/> C.A.T.V. <input checked="" type="radio"/> CONTRACTOR
GAS MATERIAL SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input type="radio"/>
*CPAU ELECTRIC CABLE SUPPLY & INSTALL.....	<input checked="" type="radio"/> <input type="radio"/> <input type="radio"/> <input type="radio"/>
ELECTRIC CONDUIT SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
ELECTRIC BOXES SUPPLY & INSTALL..... EXCAVATION.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
ELECTRIC PADS SUPPLY & INSTALL..... EXCAVATION.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
ELECTRIC TRANSFORMERS SUPPLY & INSTALL.....	<input checked="" type="radio"/> <input type="radio"/> <input type="radio"/> <input type="radio"/>
ELECTRIC INTERRUPTERS SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input type="radio"/>
CPAU ELECTRIC SWITCHES SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input type="radio"/>
TELEPHONE CONDUIT SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
TELEPHONE CABLE SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input checked="" type="radio"/> <input type="radio"/>
TELEPHONE SPLICE BOXES SUPPLY & INSTALL..... EXCAVATION.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
TELEPHONE S.A.I. PADS SUPPLY & INSTALL..... EXCAVATION.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input type="radio"/>
C.A.T.V. CONDUIT SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
C.A.T.V. SPLICE BOXES SUPPLY & INSTALL..... EXCAVATION.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
C.I.E.C. FIBER CONDUIT _____ACCEPTED _____DECLINED SUPPLY & INSTALL.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
C.I.E.C. FIBER SPLICE BOXES _____ACCEPTED _____DECLINED SUPPLY & INSTALL..... EXCAVATION.....	<input type="radio"/> <input type="radio"/> <input type="radio"/> <input checked="" type="radio"/>
● WORK TO BE PERFORMED BY THE RESPECTIVE CONTRACTOR & UTILITY COMPANIES ● ASSUME CONTRACTOR RESPONSIBILITY UNLESS OTHERWISE SPECIFIED ○ NOT APPLICABLE UNLESS OTHERWISE SPECIFIED * CPAU TO PULL CABLE INTO ENERGIZED ENCLOSURES NOTE: FOR A MORE DETAILED WORK RESPONSIBILITY BREAKDOWN, SEE CORRESPONDING MATERIAL LIST.	

THESE PLANS WERE PREPARED IN CONJUNCTION WITH THE FOLLOWING PLANS:		
	RECEIVED	APPROVED
CIVIL IMPROVEMENT PLANS/GRADING PLANS	11-01-2022	PRELIMINARY
ARCHITECTURAL ELECTRONIC FILE	10-25-2022	PRELIMINARY
APPLICANT DESIGN (GAS)		
APPLICANT DESIGN (ELECTRIC)		
TELEPHONE	06-03-2022	PRELIMINARY
C.A.T.V.		
LANDSCAPE	10-27-2022	PRELIMINARY
LIGHT LOCATIONS		
TRAFFIC SIGNAL LOCATIONS		

RADIUS DESIGN is not responsible for any subsequent changes or revisions.

OTHER UTILITIES SHOWN ARE APPROXIMATE AND BASED ON FIELD SURVEY AND AVAILABLE UTILITY INFORMATION. IT IS THE CONTRACTORS' RESPONSIBILITY TO VERIFY THE ACTUAL LOCATION AND EXTENT OF UTILITIES PRIOR TO THE COMMENCEMENT OF WORK. PHYSICAL VERIFICATION OF UTILITY LOCATIONS SHALL BE PERFORMED BY CAREFUL PROBING OR HAND DIGGING IN ACCORDANCE WITH ARTICLE 6 OF THE CAL/OSHA CONSTRUCTION SAFETY ORDERS.

CONSTRUCTION NOTES

- ALL TRENCHING, BACKFILLING AND INSTALLATION BY CONTRACTOR MUST COMPLY WITH CITY OF PALO ALTO STANDARDS.
- ALL WORK MUST COMPLY WITH CITY OF PALO ALTO(CPA), TELEPHONE, C.A.T.V., STANDARDS AND PRACTICES. ALL WORK MUST BE INSPECTED AND APPROVED BY RESPECTIVE INSPECTORS. RANDOM SOIL SAMPLES SHALL BE TAKEN FROM A MINIMUM OF THREE LOCATIONS PER 1,000' OF TRENCH. 100% OF THE SAMPLE MUST PASS THROUGH A 1/2" SIEVE AND 75% MUST PASS THROUGH A #4 SCREEN. ADDITIONAL SAMPLES MUST BE TAKEN IF EXISTING SOIL CONDITIONS CHANGE AND IS TO BE AT THE DISCRETION OF THE CPA REPRESENTATIVE ON SITE. THE SOILS MUST NOT CONTAIN ANY ROCKS THAT HAVE SHARP EDGES OR THAT MAY OTHERWISE BE ABRASIVE. THE SOILS MUST NOT CONTAIN CLODS LARGER THAN 1/2" IF TO BE USED AS SHADING, BEDDING OR LEVELING MATERIALS. COMPACTION REQUIREMENTS MUST MEET ANY APPLICABLE CPA FEDERAL, STATE, COUNTY OR LOCAL REQUIREMENTS. ANY NATIVE SOILS OR IMPORT MATERIALS USED MUST NOT HINDER THOSE EFFORTS.
- BACKFILL SHALL BE APPROVED BY THE UTILITY COMPANIES AND THE CITY. COMPACTION WILL BE TESTED AND PASSED BY THE SOILS ENGINEER.
- IF SOIL IS NOT ROCK FREE, ADD 4" DEPTH OF TRENCH FOR SAND BEDDING.
- VERIFY SPLICE BOX EXCAVATION SIZES WITH SUPPLIER(S).
- THE TRENCHING CONTRACTOR SHALL COORDINATE THE UTILITY COMPANIES' INSTALLATION.
- CONTRACTOR SHALL MAKE HIMSELF FAMILIAR WITH THE PROJECT IMPROVEMENT PLANS AND CONDUCT HIS WORK ACCORDINGLY.
- IT IS THE TRENCHING CONTRACTOR'S RESPONSIBILITY TO PROTECT IN PLACE ALL EXISTING FACILITIES. NO EXTRA PAYMENT WILL BE CONSIDERED FOR CROSSING OTHER SYSTEMS.
- RADIUS DESIGN ASSUMES NO RESPONSIBILITY FOR THE PROJECT CONDITIONS. THESE DRAWINGS WERE PREPARED USING DATA SUPPLIED BY CPA, TELEPHONE, C.A.T.V., IMPROVEMENT PLANS AND THE CITY'S VARIOUS "AS BUILT" INFORMATION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PHYSICALLY REVIEW THE PROJECT PRIOR TO SUBMITTING HIS BID.
- CONTRACTOR WILL COMPLY WITH ALL LAWS, ORDINANCES AND REGULATIONS. CONTRACTOR SHALL BE FAMILIAR WITH O.S.H.A., INDUSTRIAL SAFETY ORDERS AND SHALL CONDUCT HIS WORK ACCORDINGLY. WHEN WORKING NEAR ENERGIZED OR "HOT" EQUIPMENT, THE UTILITY OWNER SHALL BE NOTIFIED TO SUPPLY THE APPROPRIATE MAX POWER. PUBLIC SAFETY AND TRAFFIC CONTROL MEASURES ARE THE CONTRACTOR'S RESPONSIBILITY.
- THE CONTRACTOR SHALL PROTECT CONSTRUCTION STAKING. HE SHALL COORDINATE STAKING WITH THE PROJECT'S CIVIL ENGINEER.
- CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (USA) TWO WORKING DAYS PRIOR TO START OF WORK. (800) 227-2600.
- CONTRACTOR SHALL NOTIFY INSPECTORS OF ANY POTENTIAL CONFLICTS PRIOR TO START OF WORK.
- THIS PLAN IS TO BE USED FOR SOLE PURPOSE OF DIGGING THE JOINT TRENCH. SEE CPA, AT&T, AND COMCAST PLANS FOR EXACT SIZE AND NUMBER OF CONDUITS INSTALLED IN THE JOINT TRENCH. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THE CORRECT NUMBER, SIZE AND TYPES OF CONDUITS ARE INSTALLED PER THE ENGINEERED PLANS BY EACH UTILITY COMPANY.
- NOTE PLANS ISSUED AT THE PRE-CONSTRUCTION MEETING MAY BE SUBJECT TO REVISIONS, IF FINAL PLANS FROM EACH UTILITY COMPANY WERE NOT AVAILABLE AT THE START OF CONSTRUCTION.
- WATER, SEWER, DRAINS, SANITARY WASTE, FUELS (INCLUDING DIESEL AND GASOLINE), OIL, PROPANE AND OTHER VOLATILE HEAVIER THAN AIR GASES, SPRINKLER, IRRIGATION, STEAM AND OTHER "WET" FACILITIES SHALL MAINTAIN A MINIMUM OF FOUR FEET FROM THE NEAREST OUTER SURFACE OF CPA DRY FACILITIES WITH NO LESS THAN ONE FOOT OF EARTH (SOIL BARRIER) BETWEEN THE ADJACENT SIDES OF THE INDIVIDUAL TRENCHES.
- IN THE EXTRAORDINARY CASE THAT THE MINIMUM FOUR FOOT HORIZONTAL SEPARATION CANNOT BE ATTAINED BETWEEN "WET" UTILITIES AND COMPANY DRY FACILITIES, A VARIANCE MAY APPROVED BY THE LOCAL INSPECTION SUPERVISOR AND SUBMITTED TO SERVICE PLANNING SUPPORT PROGRAM MANAGER FOR APPROVAL.
- THIS JOINT TRENCH PLAN WAS PREPARED BASED ON TOPOGRAPHICAL SURVEY AS PROVIDED BY A CIVIL ENGINEER. THE CONTRACTOR IS CAUTIONED THAT EXPLORATORY WORK IS NECESSARY TO DETERMINE THE ACTUAL LOCATION OF ANY EXISTING UTILITY. RADIUS STRONGLY RECOMMENDS THAT ALL UTILITIES BE PHYSICALLY LOCATED ON THE SITE BEFORE THE ONSET OF SITE WORK. SUBSTRUCTURE LOCATIONS MAY REQUIRE FIELD ADJUSTMENT TO COMPENSATE FOR ACTUAL EXISTING UTILITY LOCATIONS.

CONDUIT NOTES

- DIRECT BURIED PRIMARY CONDUIT IS NOT AN APPROVED CONSTRUCTION METHOD. PRIMARY CONDUITS SHALL BE CONCRETE ENCASED, UNLESS OTHERWISE APPROVED BY CPAU UTILITIES ENGINEER. APPROVED CONDUIT MATERIALS:
 - SCHEDULE 40 PVC
 - B TYPE "DB 60" (SECONDARY) OR "DB 120" (PRIMARY) PLASTIC CONDUIT
 - GALVANIZED RIGID STEEL CONDUIT
- EVERY EFFORT MUST BE MADE TO OBTAIN STRAIGHT WATER-TIGHT CONDUIT LINE.
- SHARP TURNS MUST BE AVOIDED, PER THE TABLE BELOW. NORMALLY, THE PRIMARY DUCT RADIUS IS SPECIFIED. UNLESS APPROVED BY THE PROJECT ENGINEER, FACTORY OFFSETS WILL NOT BE USED.
- ALL BENDS AND SWEEPS (90 DEGREES) MUST BE ENCASED IN CONCRETE (MINIMUM 3") ALONG THE INSIDE RADIUS.
- IF THE ELECTRIC UNDERGROUND INSPECTOR DETERMINES THAT THE BOTTOM OF THE TRENCH IS ROCKY, THEN A 2" SAND BEDDING MUST BE INSTALLED BEFORE CONDUIT.
- BACKFILL IN UNIMPROVED AREAS SHALL BE 12" OF CLEAN NATURAL SAND PER CALTRANS STD SPECS SEC 19-3.025B ON TOP OF THE UPPERMOST CONDUIT, 90% COMPACTION; TOPPED WITH EXCAVATED NATIVE SOIL, 85% COMPACTION.
- BACKFILL IN IMPROVED AREAS MUST BE IN ACCORDANCE WITH CITY OF PALO ALTO STANDARD SPECIFICATIONS FOR BACKFILLING IN IMPROVED AREAS. (SECTION 21)
- ALL CONDUITS MUST BE MANDRELLED (STD. DWG DT-SS-U-1025). THIS TEST MUST BE WITNESSED BY THE ELECTRIC UNDERGROUND INSPECTOR.
- A 3/8" POLYPROPYLENE PULL LINE (MIN. 150 LBS. TEST) MUST BE INSTALLED IN EACH CONDUIT.
- CONDUIT SPACING SHALL BE MAINTAINED BY SPACERS, APPROVED BY CPA, INSTALLED NO MORE THAN 7" APART. CONDUIT MUST BE SECURELY BOUND TO THE SPACERS.
- MINIMUM COVER FOR DIRECT BURIED CONDUIT:
 - SECONDARY (NOT TRAFFIC) 24"
 - COMMUNICATION (NOT TRAFFIC) 24"
 - SECONDARY (TRAFFIC) 30"
 - COMMUNICATION (TRAFFIC) 30"
 - PRIMARY 42"
- HORIZONTAL SPACING BETWEEN SECONDARY, COMMUNICATION, TELEPHONE, AND STREET LIGHTING CABLES OR DUCTS MAY BE RANDOM UNLESS OTHERWISE SPECIFIED.
- IN EVERY CASE, VERTICAL CLEARANCE BETWEEN ELECTRIC LINES AND UTILITY LINE CROSSINGS MUST BE AT LEAST 12".
- DIRECT PRIMARY CONDUIT IS NO LONGER AN APPROVED CONSTRUCTION METHOD.

ELECTRIC UTILITIES DEPARTMENT COMMENTS & CONDITIONS


- ALL ELECTRICAL VAULT INSTALLATIONS, REMOVALS AND RELOCATION'S SHALL BE AT CUSTOMER/DEVELOPER'S EXPENSE.
- PRIMARY CONDUIT SHALL BE CONCRETE ENCASED PER CPA REQUIREMENTS.
- THE FINAL JOINT TRENCH AND VAULT DETAILS MUST BE APPROVED BY THE CITY'S ELECTRICAL ENGINEERING DEPARTMENT.
- APPLICANT SHALL NOTIFY THE ELECTRIC UTILITY INSPECTOR PRIOR TO CONSTRUCTION OF ANY ELECTRICAL UTILITY SUBSTRUCTURE.
- NO STRUCTURES PERMITTED TO BE BUILT WITHIN EXISTING PUBLIC UTILITY EASEMENTS.
- THE CONTRACTOR SHALL MAINTAIN 12" CLEAR, ABOVE AND BELOW FROM THE EXISTING UTILITIES TO NEW UNDERGROUND FACILITIES.
- APPLICANTS SHALL PROVIDE PROTECTION FOR UTILITY LINES SUBJECT TO DAMAGE. EXPOSED ELECTRIC CONDUIT OR DUCT SHALL BE INSPECTED BY THE ELECTRICAL UTILITY INSPECTOR PRIOR TO BACKFILLING.
- ANY EXTENSION OR RELOCATION OF EXISTING DISTRIBUTION LINES OR EQUIPMENT SHALL BE DONE AT CUSTOMER/DEVELOPER'S EXPENSE.

ELECTRIC CONDUIT MINIMUM BEND RADIUS FOR NEW CONSTRUCTION SERVICE			
CONDUIT DIAMETER	VERTICAL RADIUS	HORIZONTAL RADIUS	
3"	24"	36"	
4"	36"	36"	
5"	36"	60"	

NOTE:
NO MORE THAN 270 DEGREES OF BENDS ARE ALLOWED BETWEEN PULL BOXES IN A SECONDARY CONDUIT RUN.

NO MORE THAN 180 DEGREES OF BENDS ARE ALLOWED BETWEEN PULL BOXES IN A PRIMARY CONDUIT RUN.

Direct Buried Conduit



CONCRETE TRANSFORMER PAD NOTES:

- DISTURBED EARTH UNDER THE PAD SHALL BE REPLACED BY SAND OR OTHER SUITABLE MATERIAL COMPACTED TO 95% OF MAXIMUM DRY DENSITY (ASTM D-1557).
- PLACE 6" DEPTH ONE SACK PER CUBIC YARD, SLURRY IMMEDIATELY BELOW THE PAD.
- CONCRETE IS REQUIRED BETWEEN ALL CONDUITS, LEVEL TO TOP OF THE PAD.
- CONCRETE SHALL BE DESIGNED TO ATTAIN STRENGTH OF 3000 PSI IN 28 DAYS.
- AFTER PLACING, MOIST CURE CONCRETE FOR 7 DAYS.
- WOOD FLOAT FINISH TOP OF SLAB. ALL SHARP EDGES AND CORNERS TO BE FINISHED SMOOTH.
- EXPOSED HORIZONTAL SURFACES TO BE SLOPED SLIGHTLY FOR DRAINAGE.
- A MINIMUM OF 6 FEET SHALL BE MAINTAINED BETWEEN GROUND RODS.
- CAP ALL CONDUITS.
- A MINIMUM OF 3 FEET OF RADIAL CLEARANCE BETWEEN THE TRANSFORMER PAD AND ANY OTHER STRUCTURE SHALL BE PROVIDED.
- IF THE TRANSFORMER IS TO BE LOCATED IN AN AREA SUBJECTED TO VEHICULAR TRAFFIC, BARRIERS SHALL BE REQUIRED PER DT-SS-C-1005. CITY OF PALO ALTO WILL DETERMINE THE TYPE, NUMBER REQUIRED, AND LOCATION.
- PLASTIC CONDUITS SHALL BE TERMINATED WITH END BELLS. GALVANIZED STEEL CONDUITS SHALL BE TERMINATED WITH GROUND BUSHINGS. ALL CONDUITS AND ENDS WILL BE TO THE FINAL GRADE OF THE PAD.
- PRIMARY CONDUIT BENDS SHALL HAVE A MINIMUM RADIUS OF 36".
- PRIMARY CONDUITS SHALL BE LOCATED IN THE LEFT HALF OF THE CONDUIT OPENING. SECONDARY CONDUITS SHALL OCCUPY THE RIGHT HALF.
- THE TRANSFORMER PAD SHALL BE LOCATED A MINIMUM OF 3 FEET FROM ANY BUILDING OR OVERHANG.
- ALL REBAR SHALL BE A-615 GRADE 40. REBAR JOINTS SHALL BE FIRMLY AND SECURELY HELD IN POSITION BY WIRING AT INTERSECTIONS WITH NO. 16 GAGE WIRE.
- MAXIMUM NUMBER OF CONDUITS ENTERING SECONDARY SLOT SHALL BE FOUR. CONTACT THE ELECTRIC UTILITY PROJECT ENGINEER FOR DESIGN WITH MORE THAN FOUR SECONDARY.
- GROUND ROD AND CLAMP, 5/8"x8". SEE CPA STANDARD DRAWING #DT-SS-U-1001.
- TRANSFORMER ANCHORS SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S INSTRUCTIONS. EXPANSION BOLT SHALL BE "PARABOLT" BY MOLY OR APPROVED EQUAL. MINIMUM EMBEDMENT LENGTH AND EDGE DISTANCE SHALL MEET THE MANUFACTURER'S REQUIREMENTS.
- A MINIMUM OF 8 FEET CLEARANCE SHALL BE MAINTAINED FROM THE FRONT SIDE OF THE PAD. A MINIMUM OF 3 FEET CLEARANCE SHALL BE MAINTAINED ON UNOPERABLE SIDES AND BACK. ALL MEASUREMENTS ARE TAKEN FROM THE PAD.

OTHER NOTES

- EASEMENTS MUST BE GRANTED TO THE CITY OF PALO ALTO FOR SWITCH, TRANSFORMERS, AND CONDUIT ON-SITE.
- ELECTRIC METERS MUST BE IN AN AREA READILY ACCESSIBLE TO CPAU DURING ALL HOURS.
- UTILITY VAULTS, TRANSFORMERS, UTILITY CABINETS, CONCRETE BASES, OR OTHER STRUCTURES CAN NOT BE PLACED OVER EXISTING WATER, GAS OR WASTEWATER MAIN/SERVICES. MAINTAIN 1' HORIZONTAL CLEAR SEPARATION FROM THE VAULT/CABINET/CONCRETE BASE TO EXISTING UTILITIES AS FOUND IN THE FIELD. IF THERE IS A CONFLICT WITH EXISTING UTILITIES, CABINETS/VAULTS/BASES SHALL BE RELOCATED FROM THE PLAN LOCATION AS NEEDED TO MEET FIELD CONDITIONS.

GENERAL NOTES:

- JOINT TRENCH MUST BE INSTALLED ENTIRELY WITHIN AN EASEMENT. EASEMENTS FOR JOINT TRENCH SERVICE LATERALS WITHIN PROJECT ON PRIVATE PROPERTY ARE AT THE DISCRETION OF THE UTILITY COMPANIES.
- ALL DEPTHS AND RESULTING COVER REQUIREMENTS ARE MEASURED FROM FINAL GRADE.
- COVER, CLEARANCES, AND SEPARATION SHALL BE AS GREAT AS PRACTICABLE UNDER THE CIRCUMSTANCES, BUT UNDER NO CIRCUMSTANCES SHALL BE LESS THAN THE MINIMUM COVER CLEARANCE, AND SEPARATION REQUIREMENTS SET FORTH IN GENERAL ORDER 128 AND 49CFR 192.321, 49CFR 192.325, AND 49CFR 192.327. ALL FACILITIES SHALL BE ANCHORED IN PLACE PRIOR TO COMPACTION, OR OTHER MEANS SHALL BE TAKEN TO ENSURE NO MOTION OF THE FACILITIES. DIMENSIONAL REQUIREMENTS FOR SHADING, LEVELING, AND BACKFILLING SHALL BE DETERMINED SUBSEQUENT TO COMPACTION.
- TRENCH DIMENSIONS SHOWN ARE TYPICAL. TRENCH SIZES AND CONFIGURATIONS MAY VARY DEPENDING UPON OCCUPANCY AND/OR FIELD CONDITIONS. TRENCH SIZE AND CONFIGURATION MUST AT ALL TIMES BE CONSTRUCTED IN A MANNER THAT ENSURES PROPER CLEARANCES AND COVER REQUIREMENTS ARE MET. ANY "CHANGE" TO THE TRENCH WIDTH AND CONFIGURATIONS AS SHOWN IN THIS EXHIBIT MUST BE DESIGNED TO ENSURE THIS REQUIREMENT.
- IT IS PREFERRED TO HAVE NON-CPA OWNED STREETLIGHTS AT A LEVEL OTHER THAN THE GAS OR ELECTRIC LEVEL. NON-CPA OWNED STREETLIGHTS MAY BE AT THE ELECTRIC LEVEL OF THE TRENCH AS LONG AS MINIMUM CLEARANCES ARE PROVIDED AND COMPLY WITH ALL SPECIAL NOTES FOR A JOINT TRENCH WITH A SECOND ELECTRIC UTILITY.
- NON-UTILITY FACILITIES ARE NOT ALLOWED IN ANY JOINT UTILITY TRENCH, E.G., IRRIGATION CONTROL LINES, BUILDING FIRE ALARM SYSTEMS, PRIVATE TELEPHONE SYSTEMS, OUTDOOR ELECTRICAL CABLE, ETC.
- PROVIDE SEPARATION FROM TRENCH WALL AND OTHER FACILITIES SUFFICIENT TO ENSURE PROPER COMPACTION.
- MAINTAIN PROPER SEPARATION BETWEEN CPA FACILITIES AND "WET" UTILITY LINES AS DESCRIBED IN CITY OF PALO ALTO STANDARDS.
- SEPARATIONS SHALL BE MAINTAINED AT ABOVEGROUND TERMINATION POINTS.
- PROCEDURES FOR APPROVING NATIVE BACKFILL FOR SHADING OF CPA GAS FACILITIES:
 - RANDOM SOIL SAMPLES SHALL BE TAKEN FROM A MINIMUM OF 3 LOCATIONS PER 1,000' OF TRENCH. 100% OF THE SAMPLE MUST PASS THROUGH A 1/2" SIEVE AND 75% MUST PASS THROUGH A #4 SCREEN. ADDITIONAL SAMPLES MUST BE TAKEN IF EXISTING SOIL CONDITIONS CHANGE AND ARE TO BE TAKEN AT THE DISCRETION OF THE CPA REPRESENTATIVE ON SITE.
 - THE SOILS MUST NOT CONTAIN ANY ROCKS THAT HAVE SHARP EDGES OR THAT MAY OTHERWISE BE ABRASIVE.
 - THE SOILS MUST NOT CONTAIN CLODS LARGER THAN 1/2" IF TO BE USED AS SHADING, BEDDING, OR LEVELING MATERIALS.
 - COMPACTION REQUIREMENTS MUST MEET ANY APPLICABLE CPA, FEDERAL, STATE, COUNTY, OR LOCAL REQUIREMENTS.
 - AT NO TIME SHALL THE OVER SATURATION OF NATIVE SOILS BE USED TO ACHIEVE THESE REQUIREMENTS.

THE SIEVES AND SCREENS SHALL BE:

- 1/2" SIEVE: 8" DIAMETER BY 2" DEEP, STAINLESS STEEL MESH SCREEN.
- #4 SCREEN: 8" DIAMETER BY 2" DEEP, STAINLESS STEEL MESH SCREEN.

- PROCEDURES FOR APPROVING NATIVE BACKFILL FOR SHADING AT CPA ELECTRIC FACILITIES:

- RANDOM SOIL SAMPLES SHALL BE TAKEN FROM A MINIMUM OF 3 LOCATIONS PER 1,000' OF TRENCH. ADDITIONAL SAMPLES MUST BE TAKEN IF EXISTING SOIL CONDITIONS CHANGE AND ARE TO BE TAKEN AT THE DISCRETION OF THE CPA REPRESENTATIVE ON SITE.
- SHADING MATERIAL CONTAINING LARGE ROCK, PAVING MATERIAL, CINDERS, SHARPLY ANGULAR SUBSTANCES, OR CORROSIVE MATERIAL SHALL NOT BE PLACED IN THE TRENCH WHERE SUCH MATERIAL MAY DAMAGE THE CONDUITS AND/OR PREVENT PROPER COMPACTION OVER OR AROUND THE CONDUITS.
- NATIVE SOILS CONTAINING CLODS NOT TO EXCEED 6" IN DIAMETER MAY BE INCLUDED IN THE SHADING MATERIAL PROVIDED THE CLODS ARE READILY BREAKABLE BY HAND.

NOTE: SOILS CONSISTING PRIMARILY OF ADOBE, HARD COMPACT (DENSE) CLAY, AND BAY MUDDS SHALL NOT BE USED AS SHADING MATERIAL.

- AT NO TIME SHALL THE OVER SATURATION OF NATIVE SOILS BE USED TO ACHIEVE THESE REQUIREMENTS.
- REFER TO ENGINEERING DOCUMENT 062288, ITEM 13 ON PAGE 2.

- COMPETENT NATIVE SOILS ARE PREFERRED TO BE USED FOR SHADING, BEDDING, AND BACKFILLING THROUGHOUT THE TRENCH.

- WHERE NATIVE SOILS EXCEED 1/2" MINUS AND/OR WHERE GAS IS TO BE PLACED AT THE BOTTOM OF A TRENCH IN AREAS THAT EXCEED 1/2" MINUS SOIL CONDITIONS, OR WHERE THE BOTTOM OF A TRENCH IS CONSIDERED TO CONSIST OF HARD PAN, CPA APPROVED 1/2" MINUS IMPORT MATERIAL SHALL BE USED FOR SHADING AND/OR BEDDING OF GAS FACILITIES.
- CPA APPROVED IMPORT MATERIAL IS PER CGT ENGINEERING GUIDELINE 4123.
- IF A LEVELING COURSE IS REQUIRED FOR GAS FACILITIES, THE USE OF NATIVE SOILS IS PREFERRED, BUT IF 1/2" MINUS CONDITIONS ARE NOT ATTAINABLE WITH THE NATIVE SOILS, THEN THE USE OF CPA APPROVED IMPORT MATERIALS IS REQUIRED. BEDDING UNDER GAS FACILITIES WILL BE A MINIMUM OF 2" OF COMPACTED 1/2" MINUS NATIVE SOILS OR CPA APPROVED IMPORT MATERIAL.
- FOR ELECTRIC FACILITIES, REFER TO NOTE 12. THIS APPLIES TO LEVELING COURSES AS WELL AS SHADING.
- THE MINIMUM CPA APPROVED BEDDING MATERIAL MAY BE INCREASED AT THE DISCRETION OF CPA WHEN WARRANTED BY EXISTING FIELD CONDITIONS (E.G., ROCKY SOILS, HARD PAN, ETC.).
- THE USE OF ANY IMPORTED MATERIAL FOR BACKFILLING PURPOSES SHALL BE LIMITED TO THOSE SITUATIONS WHEN NATIVE SOILS DO NOT ALLOW FOR REQUIRED COMPACTION.

- THE APPLICANT IS RESPONSIBLE FOR THE REMOVAL OF EXCESS SPOIL AND ASSOCIATED COSTS.

- SERVICE SADDLES ARE THE PREFERRED SERVICE FITTINGS FOR USE THROUGHOUT THE JOINT TRENCH PROJECT. ALL PROJECTS WILL BE DESIGNED AND ESTIMATED USING SERVICE SADDLES. HOWEVER, SERVICE TEES MAY BE USED IF ALL CLEARANCES, SEPARATION, AND COVERAGE REQUIREMENTS ARE MAINTAINED.


UTILITY APPROVALS		
UTILITY	APPROVED BY	DATE
PG&E ELECTRIC		
PG&E GAS		
AT&T (PHONE)		
COMCAST (CATV)		
CITY ENGINEER		

FOR RADIUS USE ONLY QA REVIEW		
INTENT	INITIALS	REVIEW DATE
COMPOSITE		
PRE-CON		
PRE-CON		

DEVELOPER:

KSH ARCHITECTS
349 SUTTER STREET
SAN FRANCISCO, CA 94108
AMANDA BORDEN
(415) 954-1960
ABORDEN@KSHA.COM

SHEET INDEX	
JT-1	JOINT TRENCH TITLE SHEET
JT-2	JOINT TRENCH COMPOSITE
JT-3	JOINT TRENCH SECTIONS



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




RADIUS DESIGN LLC
UTILITY DESIGN CONSULTANTS & ENGINEERS
1460 MARIA LANE, SUITE 420, WALNUT CREEK, CA 94596
Tel (925) 269-4575

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
JOINT TRENCH TITLE SHEET

SCALE
N.T.S.



SHEET NUMBER

JT-1

JT-2



ARCHITECTS
KORTH SUNSERI HAGEY



UTILITY DESIGN CONSULTANTS & ENGINEERS
1460 MARIA LANE, SUITE 420, WALNUT CREEK, CA 94596
Tel (925) 269-4575

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3

PROJECT NUMBER
21003

SHEET TITLE
JOINT TRENCH SECTIONS

SCALE
N.T.S



SHEET NUMBER

JT-3

TRENCH OCCUPANCY GUIDE						
SECTION	G	T	C	S	P	OTHER
A*	X	X	X	X	X	
B*	X	X	X	X	X	
C*	X		X	X	X	
D*		X	X	X	X	
E*	X			X	X	
F*		X		X	X	
G*			X	X	X	
H*				X	X	
I†		X	X	X		
J†		X	X			
K		X	X			
L†		X	X			
M†		X	X	X		
N†		X	X	X		
O		X		X		
P†		X	X	X		
Q		X		X		
R†		X		X		
S		X	X	X		
U†		X				
V			X			
W				X		
X†						X

*THESE SECTIONS MAY OR MAY NOT CONTAIN SECONDARY CONDUIT
†THESE SECTIONS MAY OR MAY NOT CONTAIN C.L.E.C. FIBER CONDUIT

- CONTRACTOR NOTES:
- THE SYMBOLS **P** **S** **C** **T** **G** **FO** INDICATE OCCUPANCY ONLY. SEE ELECTRIC, GAS, CATV, TELEPHONE, AND FIBER OPTIC PLANS FOR EXACT SIZE AND NUMBER OF CONDUITS.
 - THIS PLAN IS TO BE USED AS A GUIDE FOR TRENCHING WIDTH AND DEPTH AND NOT CONDUIT INSTALLATION.
 - CONTRACTOR TO PROVIDE SEPARATION FROM TRENCH WALL AND OTHER FACILITIES SUFFICIENT TO ENSURE PROPER COMPACTION.
 - CONTRACTOR TO INCLUDE INCIDENTAL TRENCHING IN SPLICE BOX, VAULT, OR TRANSFORMER EXCAVATION IN AREAS WHERE NO ENTRANCE OR EXIT OF TRENCH IS SHOWN.
 - UTILITY COMPANIES RESERVE THE RIGHT TO MAKE FIELD ADJUSTMENTS AS NECESSARY.

- SOILS NOTES:
- RADIUS IS NOT RESPONSIBLE FOR ANY SOILS ENGINEERING TO DETERMINE THE ABILITY TO CONSTRUCT OR THE PROJECT CONDITIONS.
 - RADIUS ASSUMES NO RESPONSIBILITY FOR ADDITIONAL WORK DUE TO ADVERSE JOB SITE CONDITIONS.
 - PG&E WILL REQUIRE SOILS ANALYSIS FOR SUBSURFACE TRANSFORMER (IF APPLICABLE).


MINIMUM SEPARATION AND CLEARANCE REQUIREMENTS FOR JOINT TRENCHES									
	DUCT		DB		C		S		MIN. COVER
G GAS	0"	12"	12"	12"	6"	12"	12"	12"	24", 30" IN STREET
T TELEPHONE (DUCT)	12"	0"	1"	1"	12"	12"	1"	1"	24", 30" IN STREET
T TELEPHONE (DIRECT BURY)	12"	1"	0"	1"	12"	12"	1"	1"	24", 30" IN STREET
C CATV	12"	1"	1"	0"	12"	12"	1"	1"	24", 30" IN STREET
S ELECTRIC SECONDARY	6"	12"	12"	1.5"	3"	12"	12"	12"	24", 30" IN STREET
P ELECTRIC PRIMARY	12"	12"	12"	3"	3"	12"	12"	12"	36", 36" IN STREET
FO FIBER OPTIC	12"	1"	1"	1"	12"	12"	0"	0"	24", 30" IN STREET

ABBREVIATIONS:

- P** PRIMARY (PG&E)
S SECONDARY (PG&E)
C CATV (COMCAST)
T PHONE (AT&T)
G GAS (PG&E)
FO FIBER OPTIC (C.L.E.C.)


SHEET INDEX

JT-1 JOINT TRENCH TITLE SHEET
JT-2 JOINT TRENCH COMPOSITE
JT-3 JOINT TRENCH SECTIONS



UNIVERSITY AVE


BYRON STREET



Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
site	Illuminance	Fc	1.37	37.3	0.0	N.A.	N.A.

Luminaire Schedule									
Symbol	Qty	Label	Arrangement	Description	Tag	LLF	Luminaire Lumens	Luminaire Watts	Total Watts
'B'	14	EC-40571-W27	Single	EC-40571-W27 Rev_2		0.850	664	23.1	323.4
'A'	14	EVO4_27_10_AR_MD_LSS (1)	Single	EVO4_27_10_AR MD LSS		0.850	923	8.8	123.2

1 SITE PHOTOMETRIC PLAN



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ARCHITECTS
KORTH SUNSERI HAGEY



PROJECT 2021-1343
CONTACT KRISTINA SANTI


135 Main Street, Suite 400
San Francisco, CA 94105
TEL 415.489.7240
www.interfaceengineering.com

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2

ADD PREVIOUS
AND CURRENT
SUBMITTAL
DATES/TITLES (SEE
CONSULTANT TITLE
BLOCK)

PROJECT NUMBER
21003


SHEET TITLE
SITE PHOTOMETRIC PLAN



SHEET NUMBER

E0.1

EVD4 | GOTHAM ARCHITECTURAL DOWNLIGHTING | 1400 Lester Road Cary, NC 27513 | P 800-705-SERV (7378) | gothamlighting.com
page 1 of 8 | © 2014-2022 Acuity Brands Lighting Inc. All Rights Reserved. Rev. 03/08/22 Specifications subject to change without notice.

EV04 | GOTHAM ARCHITECTURAL DOWNLIGHTING | 1400 Lester Road Conyers, GA 30012 | P 800-705-SERV (7378) | gothamlighting.com
 © 2014-2022 Acuity Brands Lighting Inc. All Rights Reserved. Rev. 03/08/22 Specifications subject to change without notice.  gotham

Ugarni Lighting USA reserves the right to change specifications without prior notice, please contact factory for latest information. Due to the continual improvements in LED technology data and components may change without notice.

EVD4 | GOTHAM ARCHITECTURAL DOWNLIGHTING | 1400 Lester Road Conyers, GA 30012 | P 800-705-SERV (7378) | gothamlighting.com
 page 3 of 8 | © 2014-2022 Acuity Brands Lighting Inc. All Rights Reserved. Rev. 03/08/22 Specifications subject to change without notice.

Lighting USA reserves the right to change specifications without prior notice, please contact factory for latest information. Due to the continual improvements in LED technology, data and components may change without notice.

PROJECT NUMBER

SHEET TITLE

LIGHT FIXTURE CUT SHEETS

N.T.S.

SHEET NUMBER
