

SECTION 4

SITE MAINTENANCE AND CLEAN-UP

- 4-1 General** - Throughout the construction period, the site shall be maintained in a neat and orderly condition at all times in accordance with the provisions contained herein described.
- 4-2 Daily Clean-Up** - The project site shall be inspected daily and cleared of all scrap, debris and waste material not required for construction of the work. Any material remaining on site shall be covered with tarps, and comply with Section 8 (stormwater pollution prevention) and other PAMC requirements. Waste material shall be disposed of at an approved and properly permitted and licensed solid waste disposal facility. Garbage, mixed construction and demolition materials, and mixed recycling shall be collected by the City's exclusive waste collection contractor.
- 4-3 Excess Material** - Except for recyclable inert solids and building materials as specified in Section 24, "Inert Solids and Building Materials Recycling", of these Standard Drawings and Specifications, excess material excavated may be deposited at a location designated by the Engineer or shall be disposed of properly at a permitted facility. Material to be deposited shall be free of deleterious material.
- 4-4 Final Cleaning** - Before final inspection of the work, the Contractor shall clean the project site and all grounds occupied thereby in connection with the work of all rubbish, excess materials, false work, temporary structures, equipment and other items, if directed by the Engineer. All parts of the work shall be left in a neat and presentable condition.

END OF SECTION