

Grate stake as manufactured by J.R. Partners

Tree as specified by City

KIVA model frame and grate as manufactured by Urban Accessories

3" perforated plastic flexible drain pipe with filter fabric wrap. Finish pipe ends with perforated end caps or slotted grates.

PCC Curb and Gutter

Rootball

Don't disturb soil under rootball

Limits of excavation

**SECTION A-A**


**NOTES**

1. Contact Underground Service Alert (USA) @ (800) 642-2444 at least 48 hours prior to beginning excavation work to located existing utilities.
2. Soil, concrete and other materials spilled on street, sidewalk, and planting area shall be cleaned up immediately by Contractor.
3. If tree planting is delayed after tree wells are constructed, holes shall be filled and barricades secured to grates.

Backfill with approved loam topsoil around rootball and water at time of planting.

Rev	By	Date
0	SGW	12/14/92
1	JT	08/14/06
2	HN	03/19/07

**Tree Well Detail**

Approved by:  
  
 PE No. 35411  
 Date 5/14/07

Scale: NTS

**City of Palo Alto Standard**

Dwg No. **603**